



Jon S. Corzine
Governor

State of New Jersey
Department of Community Affairs
Division of Codes and Standards
PO Box 802
Trenton, New Jersey 08625-0802



Susan Bass Levin
Commissioner

BULLETIN NO.

07-1

Date: **January 2007** Subject: **Premanufactured**
Code Ref. Update: **November 2008** **Construction**

Reference: N.J.A.C. 5:23-4A,
N.J.A.C. 5:23-4B,
N.J.A.C. 5:23-4D,
N.J.A.C. 5:23-2.15(f)1.ix,
N.J.A.C. 5:23-2.22

“Premanufactured construction” is a generic term which is used to include all types of factory-built construction. The following chart indicates various categories of premanufactured buildings covered under the New Jersey Uniform Construction Code (UCC) and lists where in the code to find specific requirements for the critical items in each category. A construction permit is required for all on-site work related to installation of certified premanufactured construction. The on-site work includes but is not limited to foundation system, installation, assembly, external utility connections, etc. The local municipal enforcing agency is responsible for inspection and approval of all on-site work.

Approved and certified premanufactured construction, which means that it carries proper insignia of certification in accordance with the UCC, shall be acceptable for installation in New Jersey.

The UCC definitions of the terms used in this bulletin are as follows:

Building Component – Any subsystem, subassembly, or other system of closed construction that is designed for use in or as part of a structure. “Building component” may include structural, electrical, mechanical, plumbing, and fire-protection systems, and other systems affecting health and safety.

Building Element – An element of a building (such as fire walls, fire separation walls, wall panels, prestressed/prefabricated floor or roof panels, and pre-engineered structural frames) built in accordance with the UCC.

Industrialized/Modular Building – Any building of closed construction including but not limited to modular housing that is factory-built for single family and multifamily (including closed-wall, panelized housing), and other modular, nonresidential buildings. “Industrialized/modular building” does not include any structure subject to the requirements of the National Manufactured Home

BULLETIN

BULLETIN NO.

07-1

BULLETIN

Construction and Safety Standards Act of 1974 (i.e., manufactured buildings excluding HUD units).

Manufactured (Mobile) Home (a.k.a. HUD unit) – A structure, transportable in one or more sections, which in the traveling mode is eight body feet or more in width or 40 body feet or more in length, or when erected on the site is 320 or more square feet, and which is built on a permanent chassis and designed to be used as a dwelling with or without a permanent foundation when connected to the required utilities, and includes the plumbing, heating, air conditioning, and electrical systems contained therein; except that such term shall also include any structure which meets all of the requirements of this paragraph except the size requirements, and with respect to which the manufacturer has voluntarily filed a certification required by the Secretary of the United States Department of Housing and Urban Development (HUD) and complies with the standards established under 42 U.S.C. Section 5401, et seq.

Recreational Park Trailer – A trailer-type unit that is built on a single chassis mounted on wheels and has a gross trailer area not exceeding 400 square feet (37.15 sq. meters) in set-up mode that meets the criteria listed in the Recreational Park Trailer Subcode at N.J.A.C. 5:23-4D.2(a).

Premanufactured Construction¹
N.J.A.C. 5:23-1.4 and 2.22

	Manufactured (Mobile) Homes	Manufactured Home Add-on Units	Building Elements	Industrialized/ Modular Buildings	Building Components	Recreational Park Trailers (RPT)
Certification Required	N.J.A.C. 5:23-1.4 N.J.A.C. 5:23-4B.3(a)	N.J.A.C. 5:23-4B.3(b)	N.J.A.C. 5:23-4.26(a)	N.J.A.C. 5:23-4A.4 N.J.A.C. 5:23-4A.7	N.J.A.C. 5:23-4A.4 N.J.A.C. 5:23-4A.7	N.J.A.C. 5:23-4D.2 N.J.A.C. 5:23-4D.4
Acceptability	N.J.A.C. 5:23-2.22(a) N.J.A.C. 5:23-4B.5(a)	N.J.A.C. 5:23-2.22(a) N.J.A.C. 5:23-4B.5(b)	N.J.A.C. 5:23-4.26(a)	N.J.A.C. 5:23-2.22(a) N.J.A.C. 5:23-4A.3(b)	N.J.A.C. 5:23-2.22(a) N.J.A.C. 5:23-4A.3(b)	N.J.A.C. 5:23-2.22(a) N.J.A.C. 5:23-4D.6
Construction Standards	Federal M.H. Construction and Safety Standards Part 3280	NJUCC/M.H. Subcode N.J.A.C. 5:23-3.19	NJUCC N.J.A.C. 5:23-4.26(a)	NJUCC N.J.A.C. 5:23-4A.5	NJUCC N.J.A.C. 5:23-4A.5	NJUCC/RPT Subcode ANSI A119.5 N.J.A.C. 5:23-4D.3
Insignia (Label) Requirements	Federal M.H. insignia N.J.A.C. 5:23-4B.5 3280.11	NJDCA M.H. Add-on insignia N.J.A.C. 5:23-4B.7(c)	None N.J.A.C. 5:23-4.26(a)	I.B.C. insignia Part IC, Section 4 of UAP ²	I.B.C. insignia Part IC, Section 4 of UAP ²	N.J.A.C. 5:23-4D.4
On-site Work (Installation, assembly, etc.)	On-site work (foundation, etc.) plans and specs signed and sealed by NJ P.E. or R.A. ³ N.J.A.C. 5:23-2.15(f)1.ix	On-site work (foundation, etc.) plans and specs signed and sealed by NJ P.E. or R.A. ³ N.J.A.C. 5:23-2.15(f)1.ix	Plans and specs signed and sealed by NJ P.E. or R.A. ³	On-site work (foundation, etc.) plans and specs signed and sealed by NJ P.E. or R.A. ³ N.J.A.C. 5:23-2.15(f)1.ix	Plans and specs signed and sealed by NJ P.E. or R.A. ³ N.J.A.C. 5:23-2.15(f)1.ix	On-site work (anchoring, etc.) plans and specs signed and sealed by NJ P.E. or R.A. ³ N.J.A.C. 5:23-2.15(f)1.ix
Required Inspections by Local Enforcing Agency	N.J.A.C. 5:23-2.22 1. Visible signs of damage 2. Visible code (federal standards) violations 3. All on-site work including assembly, installation, external utility systems, foundation, etc. 4. Nondestructive testing (plumbing, electrical, etc.)	N.J.A.C. 5:23-2.22 1. Visible signs of damage 2. Visible code (federal standards) violations 3. All on-site work including assembly, installation, external utility systems, foundation, etc. 4. Nondestructive testing (plumbing, electrical, etc.)	N.J.A.C. 5:23-2.22 1. Visible signs of damage 2. Visible code (NJUCC) violations	N.J.A.C. 5:23-2.22 Part IV, Section 6(B) & (C) of UAP 1. Visible signs of damage 2. Visible code (NJUCC) violations 3. All on-site work including assembly, installation, external utility systems, foundation, etc. 4. Nondestructive testing (plumbing, electrical, etc.)	N.J.A.C. 5:23-2.22 Part IV, Section 6(B) & (C) of UAP 1. Visible signs of damage 2. Visible code (NJUCC) violations 3. All on-site work including assembly, installation, external utility systems, foundation, etc. 4. Nondestructive testing (plumbing, electrical, etc.)	N.J.A.C. 5:23-2.22 1. Visible signs of damage 2. Visible code (RPT Subcode) violations 3. All on-site work including assembly, installation, external utility systems, anchoring, etc. 4. Nondestructive testing (plumbing, electrical, etc.)

¹ Premanufactured construction is a generic term used for factory-built construction.

² UAP – Uniform Administrative Procedures of the Industrialized Buildings Commission (I.B.C.) adopted by reference at N.J.A.C. 5:23-4A.10 and can be viewed at www.interstateibc.org/forms.htm.

³ See Bulletin No. 96-2 re: signing and sealing of plans. Requirements for sealed plans waived in case of a single-family homeowner building his/her own private residence – N.J.A.C. 5:23-2.15(f)1.ix.