## NJM Hammonton Regional Operations Facility





The Gale Construction Company LLC

Princeton Hydro

#### A site with sustainability in mind

#### 3rd Floor Fit-out qualified as LEED Silver

Sites Brownfield Redevelopment Water quantity Water quality Heat island effect reduction Light pollution reduction

#### Water Efficiency

Potable water use reduced by 34%

Energy and Atmosphere

Connected lighting power reduced by 35.5%

ENERGY STAR = 92.5%

Enhanced commissioning

Materials and Resources



80.3% of construction materials recycled (diverted from landfill)
22% of construction materials constructed from recycled materials
26% of construction materials manufactured within 500 miles

#### Indoor Air Quality

ASHRAE Standard 62.1-2007
No smoking on property
Construction IAQ Management Plan
Low-emitting materials (paints & coatings, flooring, wood and agrifiber, furniture and seating Thermal comfort

# From concept to reality



#### Site Layout and Constraints



•55-acre site.

•Historic peach orchard (remediated for historic pesticides, 26,000 cy removed from the site).

•Adjacent to historic gravel mine.

•Limited stormwater infrastructure in vicinity.

•Within the NJ Pinelands.

•Required to infiltrate difference between 10-year pre- and post-development runoff.

#### **Historic Pesticides**

NJM first remediated site to the residential standard.
 Historic peach orchard
 Dieldrin and arsenic contaminated soils
 Removed 26,000 cubic yards of soil






# Look into site's ability to manage stormwater

Client did something that should be considered by others:

Asked us to determine the maximum area of impervious cover that the site could handle in relation to the regulations.


Then backed into zoning to see what size building they could construct.





## Conducted appropriate on site testing

Desktop review of onsite soils Aura soils limitations revealed ➢Clay bridging between soil particles Fragipan located between 22 and 60 inches.



#### Field Work

Test pits and borings followed a 2 step process:


Step 1: General investigation to determine appropriate locations for basins and other facilities

Step 2: BMP Specific Investigation
 Installed 5 wells on site to assess
 regional groundwater and fluctuations






#### **Data Reviewed**



#### Data Reviewed





### Final Layout and Integration of BMPs



## Final Layout and Integration of BMPs

- 8 Bio-Infiltration Basins
- 1 Wetland Basin
- 6 Bio-Infiltration Islands
- 1 Bio-Retention Swale
- Roof rainwater harvesting (120k gallons)
- (Phase II) Pervious pavement
- Meadow creation/preservation



### Addressing at the source

Seepage pit/sumps for pretreatment


All areas disturbed to remain non-impervious were rototilled and where necessary, compost amended.





## Proposed Methods for Preparation of Infiltration Zones

- Need to break-up clay bridging and layers.
- Need to penetrate soils with fragipans.
- Need to reduce bulk density of infiltration zones to achieve higher permeability rates and increase temporary subsurface storage.
- Need to understand underlying aquifer.
- Mounding Analysis was critical in determining effectiveness of infiltration areas.



## Solutions for Preparation of Infiltration Zones

- Excavate and remove all fragipans and materials classified as clayey sands and silts.
- Dig and drop all areas to a depth of 2x maximum expected water depth and at least 2x water depth into underlying sandy stratums
- **Top 3** feet mixed with organics (i.e. whole leaf/fine leaf composite).





Infiltration can be optimized by excavating and backfilling the subgrade to a depth of 2 times the expected maximum water depth in the basin.



Remove deleterious soils



**Deliver organics** 





Spread organics



After deep mix, mix in organics to 3 feet

Test to ensure infiltration rate goals

#### 120,000 gallon cistern to collect <u>roof</u> runoff and use for landscape irrigation



#### Lessons Learned

There is a need to change the culture of earthwork contractors and approach to construction.
Need to develop owner expectations before you start design.
While 2 feet of separation is mandated, even 4 feet is pushing the limitations to avoid mounding failure.
While infiltration can be estimated, final results can vary, impacting vegetation cover types. Need to plan to re-visit species once basins are complete.























# From concept to reality

#### concept



#### Now let's take a walk

design

reality

