

**Osprey Management Project
Endangered & Nongame Species Program
NJ Division of Fish & Wildlife**

Material list for building one Osprey Nest Platform

<i>Approximate (2006)</i>				
Item	Quantity	Size	Description	Unit price
<i>Lumber</i>				
Pole	1	16'	6"x6" pressure treated	\$40.00
Box frame, box side brace, platform brace	2	12'	2"x6" pressure treated	\$16.00
Perch / brace	1	12'	2"x4" pressure treated	\$6.00
Wire cloth (optional)	3'	3'	2"x4" galv. hardware cloth	\$3.00
<i>Fasteners</i>				
Base to pole	2	3/8" x 6"	galvanized lag bolts	\$1.30
	2	3/8"	galv. flat washers	\$0.12
Box to base	8	3"	stainless or galv. wood screws	\$0.25
4 box corners	12	3"	galv. wood screws	\$0.40
Brace to base	2	3/8" x 8"	galv. carriage bolts	\$1.80
	2	3/8"	galv. flat washers	\$0.12
Brace to pole	1	5/8" x 10"	galv. hex bolt	\$2.60
	2	5/8"	galv. flat washers	\$0.34
Fasten wire to box	40	3/8"	galv. fence staples	\$0.40
<i>Predator Guard</i>				
Aluminum flashing	1	24"x ~ 25"	.092 gauge (brown painted)	\$5.00
Roofing nails	10	1 1/2"	1.5" Galvanized roofing nails	\$2.00
Estimated Total Cost				\$79.33

For nest placement help refer to our nest structure placement information page.

Please let us know where you place the nest platform(s) and when they are used by a pair of ospreys.

We will include the site in our triennial surveys. Thank you for helping Ospreys in New Jersey.

Kathy Clark, Principal Zoologist
Endangered & Nongame Species Program
2201 Route 631
Woodbine, NJ 08270
(609) 628-2103