

Project	County	Municipality	Construction Type	Description	Program Construction Funding	Anticipated Month of Award	Estimated Contract Value	Estimated Duration (months)	Status of award (updated 8/2/12)
<b>FY2012</b>									
Rt 30/130 Collingswood/Pennsauken (Phase B)	Camden	Collingswood Boro Camden City Pennsauken Twp.	Oper. & Safety Improvements	Replacement of the Cooper River bridge. Route 30/130 will be widened northbound to three travel lanes from Haddon Avenue to North Park Drive. In addition, sidewalks will be added on both sides	Prop.Federal-FY'12	12/1/11	\$25M-\$50M	23	Awarded 12/12/11 to South State Inc. (\$25.7 m) Addenda included diesel reqts.
I-78 Union/Essex Rehabilitation, Contract B	Union Essex	Hillside Twp. Newark City Union Twp.	Oper. & Safety Improvements	Pavement will be rehabilitated through pavement removal and replacement, concrete rubbilization where applicable and bituminous overlay. Structure work includes concrete deck repair, deck joint reconstruction, installing preformed elastomeric joint sealers and resealing filled joints. Also, all bridges will be overlaid with 2" of HMA, except one bridge (Str. # 0723-161) due to underclearance restrictions	Prop.Federal-FY'12	12/1/11	\$50-100M	26	Awarded to Ferreira Construction and Crisdel Group, (Joint Venture) for \$72.3 m.
Rt 29, Memorial Drive	Mercer	Trenton City	Oper. & Safety Improvements	Extension of existing Barrack Street from the West Lafayette Street intersection, past the War Memorial building to existing Memorial Drive.	Federal-FY'11	1/1/12	<\$5M	10	Awarded 11/3 to Joseph Defino Trucking.
South Marginal St., Bridge over Park Avenue	Hudson	Weehawken Twp.	Bridge Improvements	Replacement of the North Marginal Street bridge deck over Park Avenue in Weehawken, Hudson County.	Prop.Federal-FY'12	1/1/12	1.3M	6	Awarded to Sparwick Contracting 4/5/12 for 1.3M
Rt 18 Extension Sec 3A	Middlesex	Piscataway Twp.	Oper. & Safety Improvements	Existing Hoes Lane from the Hoes Lane Extension to I-287 will be rehabilitated and will remain a four-lane roadway with signal modification	Federal-FY'11	9/1/11	\$25M-\$50M	21	Awarded 11/30/11 to Intercounty Paving (\$25.9). RFP included diesel reqts.
Rte 322 over Big Ditch, Bridge Replacement	Atlantic	Hamilton Twp	Bridge Improvements	Replace bridge #0119-156 over Big Ditch	Federal-FY11	9/1/11	<\$5 m	11	Awarded 10/12/11 to Agate Construction for \$3.6.
Rt 130 Sec 16	Middlesex	No. Brunswick Twp.	Oper. & Safety Improvements	Provide geometric improvements to Route 130 at its intersection with Adams Lane, and at Maple Mead Road	Federal-FY'11	11/1/11	\$5M-\$10M	13	Awarded 11/29/11 to Green Cosntruction (\$8.5). RFP included diesel reqts.
Rt 18 SB from S of Rt 138 to S of Deal Rd Resurfacing	Monmouth	Ocean Twp. Wall Twp. Neptune Twp.	Roadway Improvements	Resurface pavement	Prop.Federal-FY'12	12/1/11	<\$5M	9	Awarded 3/15/11 to Earle Asphalt Co
Rt 120 MP 0.00 to MP 2.09 Resurfacing	Bergen	Carlstadt Boro	Roadway Improvements	Resurface pavement	Prop.Federal-FY'12	3/1/12	<\$5M	10	Awarded 3/14/11 to Della Pello
Rt 27 Sec 3E Six Mile Run Bridge	Middlesex Somerset	No. Brunswick Twp. Franklin Twp.	Bridge Improvements	The existing structure will be replaced on the same alignment. The existing structure has two 11-foot travel lanes and shoulders of varying width. The new structure will have two 12-foot travel lanes and 10-foot shoulders, along with a sidewalk on the western side of the structure.	Prop.Federal-FY'12	12/1/13	<\$5M	13	Moved to 2013 Budget by NJDOT

Yellow - Urban Center

Blue - Within 2 miles of Urban Center

Attachment 1:  
Construction projects for which retrofit technology will be required under Diesel Executive Order #60.

Project	County	Municipality	Construction Type	Description	Program Construction Funding	Anticipated Month of Award	Estimated Contract Value	Estimated Duration (months)	Status of award (updated 8/2/12)
<b>FY2012</b>									
<i>Rt. 27 South Plainfield Branch</i>	<i>Middlesex</i>	<i>Metuchen Boro</i>	<i>Bridge Improvements</i>	<i>Replacement of structure (#1218-152) over Greenway (abandoned railroad corridor). Intersection improvements at Lake Avenue, including new traffic signal and channelization.</i>	<i>Prop.Federal-FY'12</i>	<i>4/1/12</i>	<i>&lt;\$5M</i>		<i>Awarded to Ritacco Construction on 5/25/12 for 3.8M</i>
<i>Rt. 27 N of Evergreen Street to vicinity of Elizabeth River Resurfacing</i>	<i>Middlesex Union</i>	<i>Edison Twp.; Woodbridge Twp.; Rahway City</i>	<i>Roadway Improvements</i>	<i>Pavement Rehabilitation at the following locations: mp 23.8-26.7; mp 27.2-34.1.</i>	<i>Prop.Federal-FY'12</i>	<i>Estimate 8/2012</i>	<i>\$5-10M</i>	<i>10 mos</i>	<i>Awarded to Joseph DeFino Trucking Co. Inc. on 11/21/12</i>
<i>Rt. 4 over Flat Rock Brook</i>	<i>Bergen</i>	<i>Englewood City</i>	<i>Bridge Improvements</i>	<i>This project will replace the existing deck on the Route 4 over Flat Rock Brook structure (Str. # 0206-181).</i>	<i>Prop.Federal-FY'12</i>	<i>5/1/12</i>	<i>&lt;\$5M</i>	<i>not set</i>	<i>Awarded to J.F.Creamer &amp; Son J/V Joseph M. Sanzari, Inc on 12/2/12</i>
<i>Rt. 17 S of Terrace Ave. to S of W. Saddle River Road Resurfacing</i>	<i>Bergen</i>	<i>Hasbrouck Heights; Hackensack City; Lodi Boro</i>	<i>Roadway Improvements</i>	<i>Mill and pave resurfacing project.</i>	<i>Prop.Federal-FY'12</i>	<i>5/1/12</i>	<i>\$5-10M</i>	<i>11 mos</i>	<i>Awarded 5/25/12 to Dello Pello</i>
<i>Rt. 1 various locations from N of College Road to NJ 91 Connector</i>	<i>Middlesex</i>	<i>Plainsboro Twp.; No. Brunswick Twp.; So. Brunswick Twp.</i>	<i>Roadway Improvements</i>	<i>Pavement rehabilitation.</i>	<i>Prop.Federal-FY'12</i>	<i>6/1/12</i>	<i>\$5-10M</i>	<i>5 mos</i>	<i>Awarded 5/17/12 to Schifano Construction for 8.5 M</i>
<i>Rt. 1 NB, S of CR 514 to I-287 Resurfacing</i>	<i>Middlesex</i>	<i>Edison Twp</i>	<i>Roadway Improvements</i>	<i>This is a mill and pave resurfacing project in Middlesex County. Preventive Maintenance Resurfacing</i>	<i>Prop.Federal-FY'12</i>	<i>6/1/12</i>	<i>&lt;\$5M</i>	<i>5 mos</i>	<i>Awarded on 4/30/12 to Tilcon, NY lic. For 2.9M.</i>
<i>Rt. 28 from Branch of Green Brook to Hamilton</i>	<i>Middlesex Somerset</i>	<i>No. Brunswick Twp. Franklin Twp.</i>	<i>Bridge Improvements</i>	<i>Pavement rehabilitation.</i>	<i>Prop.Federal-FY'12</i>	<i>5/1/12</i>	<i>&lt;\$5M</i>	<i>11 mos</i>	<i>Awarded to Schifano Construction on 5/18/12</i>