

Table 2.5-2

Land Requirements for Pipeline Facilities within the Delaware River Basin<sup>1</sup>

River Basin	Approximate Length/ No. of Sites	Temporary Workspace for Construction (acres)	Additional Temporary Workspace for Construction (acres)	Permanent Easement for			Total Workspace for Construction (acres)	Operational ROW (acres) <sup>6</sup>
				Existing <sup>2</sup>	Partially Existing	New		
Pipeline								
Upper Delaware	102.4 (mi)/4	542.9	350.0	20.7	31.7	565.4	1510.8	370.8
Access Roads <sup>3</sup>								
Upper Delaware	24.3 (mi)/85	0.0	0.0	0.0	0.0	90.3	90.3	-
Pipeyards								
Upper Delaware	333.7 (ac)/10	0.0	333.7	0.0	0.0	0.0	333.7	-
Above Ground Facilities <sup>4</sup>								
Upper Delaware	52.2 (ac)/14	1.7	0.4	0.0	1.4	48.7	52.2	-
Staging Areas								
Upper Delaware	28.3 (ac) /7	0.0	28.3	0.0	0.0	0.0	28.3	-
Total Project								
Upper Delaware	126.7(mi) /414.2 (ac) <sup>5</sup>	544.6	712.4	20.7	33.0	704.4	2015.2	-
Project Total							2015.2	370.8

**Notes:**

1. The totals shown on this table may not equal the sum of addends due to rounding.
2. Only includes existing third party easement overlapping proposed project permanent 50 foot ROW, within limits of construction.
3. Estimated Temporary Workspace for Construction includes access roads (new and existing).
4. This table does not specify valves and launcher/receivers that will be constructed on the pipeline segments since the land requirements for these facilities are within the land requirements for the pipeline segments.
5. Mileage of Pipeline and Access Roads, Acreage of Pipeyards, Staging Areas, and Above ground facilities.
6. Operational ROW is calculated with a 30 foot ROW within limits of construction.