

AMENDED DRAFT FY 2008-11
STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM
New Jersey Department of Transportation Projects

PROJECT NAME	Project ID No.	TIP No.
Almond Road (CR 540), Centerton Road to the Maurice River, Resurfacing	S0706	S0706

This project will provide for the resurfacing and rehabilitation of Almond Road (CR 540) from Centerton Road (CR 553) to the Maurice River. This project is multi-year funded under the provisions of Section 13 of P.L. 1995, c.108. Total Federal aid needed is anticipated to be \$3.5 million for construction.

COUNTY: Salem

MUNICIPALITY: Pittsgrove Twp.

MILEPOSTS: 25.89 - 31.30

STRUCTURE NO.:

LEGISLATIVE DISTRICT: 3

SPONSOR: Salem County

PROGRAM CATEGORY: Local Aid - Local Roadway Improvements

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
SJTPO	DES	STP-SJ	\$480,000				
SJTPO	CON	STP-SJ			\$1,500,000	\$2,000,000	

PROJECT NAME	Project ID No.	TIP No.
Commissioner's Pike, Phase II, Route 40 to Salem/Gloucester County Line, CR 581	S0005	S0005

This project will provide for the roadway resurfacing from Route 40 to the Gloucester County line, excluding the County Line Bridge at Oldman's Creek. The project will consist of milling and overlay of 12-foot lanes (one in each direction) with 3-foot dense grade aggregate, continuous shoulders, drainage improvements, guiderail improvements, signage, pavement marking and traffic striping.

COUNTY: Salem

MUNICIPALITY: Upper Pittsgrove Twp.

MILEPOSTS: 10.62 - 13.00

STRUCTURE NO.: N/A

LEGISLATIVE DISTRICT: 3

SPONSOR: Salem County

PROGRAM CATEGORY: Local Aid - Local Roadway Improvements

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
SJTPO	CON	STP-SJ	\$800,000				

AMENDED DRAFT FY 2008-11
STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM
New Jersey Department of Transportation Projects

PROJECT NAME	Project ID No.	TIP No.
Route 295, Northbound, South of Route 130 to South of Pedricktown-Woodstown Road, Resurfacing	06414	06414

The existing roadway typically consists of three 12-foot asphalt travel lanes with 12-foot asphalt shoulders. The opposing traffic is separated by a grass median. The roadway condition is generally fair to poor, exhibiting moderate to high severity raveling, rutting, fatigue cracking in wheel paths, and isolated patching. The outside shoulder is in fair to poor condition. It is proposed to mill and resurface the entire roadway with Superpave hot mix asphalt. All inlets and other roadway utility hardware will be adjusted to final grade. Raised pavement markers will be reinstalled. Deteriorated curb and curb with existing low reveal will be reconstructed. No utility work is anticipated. Only resurfacing and incidentals required to facilitate the resurfacing as outlined in the scope of work for 3R projects will be done.

Bridge decks within the project limits do not require rehabilitation; therefore, pavement will be transitioned to meet the bridge decks. Existing vertical clearance will be maintained at all underpasses.

COUNTY: Salem

MUNICIPALITY: Pennsville Twp. Carneys Point Twp. Oldmans Twp.

MILEPOSTS: 0.90 - 8.00

STRUCTURE NO.: N/A

LEGISLATIVE DISTRICT: 3

SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Highway Resurfacing

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
SJTPO	CON	STATE		\$7,250,000			