

**FY 2008-11**  
**STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM**  
**New Jersey Department of Transportation Projects**

<b>PROJECT NAME</b>	<i>Project ID No.</i>	<i>TIP No.</i>
<b>Brass Castle Road Bridge over Pohatcong Creek, CR 623</b>	NS9905	NS9905

Brass Castle Road (Bridge No. 2102215, County Route 623) over the Pohatcong Creek in Washington Township is structurally deficient and functionally obsolete. This project includes the replacement of the existing deficient bridge with a new structure that meets current NJDOT design standards. The new bridge will have two travel lanes, shoulders and sidewalks.

COUNTY: Warren

MUNICIPALITY: Washington Twp.

MILEPOSTS: N/A

STRUCTURE NO.: 2102215

LEGISLATIVE DISTRICT: 23

SPONSOR: Warren County

PROGRAM CATEGORY: Bridge Preservation - Local Bridges

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
NJTPA	CON	STP-NJ	\$950,000				

<b>PROJECT NAME</b>	<i>Project ID No.</i>	<i>TIP No.</i>
<b>Cemetery Road Bridge over Pequest River</b>	NS9314	NS9314

Cemetery Road crosses the Pequest River in Independence Township. The bridge is in poor condition and is deteriorating. It is eligible for the National Register of Historic Places. The structure will be replaced.

COUNTY: Warren

MUNICIPALITY: Independence Twp.

MILEPOSTS: N/A

STRUCTURE NO.: 2101202

LEGISLATIVE DISTRICT: 23

SPONSOR: Warren County

PROGRAM CATEGORY: Bridge Preservation - Local Bridges

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
NJTPA	ROW	STP-NJ	\$50,000				
NJTPA	CON	STP-NJ			\$1,000,000		

**FY 2008-11**

**STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM**

**New Jersey Department of Transportation Projects**

<b>PROJECT NAME</b>	<b>Project ID No.</b>	<b>TIP No.</b>
<b>Newburgh Road Bridge over Musconetcong River</b>	<b>NS9909</b>	<b>NS9909</b>

Built in 1908, the Newburgh Road Bridge over the Musconetcong River in Washington and Mansfield Townships in Morris and Warren Counties is functionally obsolete. The existing bridge is a two span structure. The bridge deck consists of simply supported multiple rolled steel stringers and is supported on stone masonry abutments and a mid-span pier. The bridge has inadequate deck geometry, inadequate turning radii, substandard lane widths, and has been prioritized as a high priority for in-depth scour evaluation due to Alternatives will be considered for rehabilitation or replacement of the bridge. Morris County is the lead on this project.

COUNTY: Morris Warren  
 MUNICIPALITY: Washington Twp. Mansfield Twp.  
 MILEPOSTS: N/A  
 STRUCTURE NO.: 1401196  
 LEGISLATIVE DISTRICT: 24 23 SPONSOR: Morris County  
 PROGRAM CATEGORY: Bridge Preservation - Local Bridges

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
NJTPA	DES	STP-NJ	\$375,000				
NJTPA	ROW	STP-NJ		\$425,000			
NJTPA	CON	STP-NJ			\$3,250,000		

<b>PROJECT NAME</b>	<b>Project ID No.</b>	<b>TIP No.</b>
<b>Route 57, Corridor Scenic Preservation</b>	<b>97062A</b>	<b>97062A</b>

This is an innovative pilot program to restore, preserve and enhance scenic beauty and to preserve mobility in the Route 57 corridor from Route 22 to Route 182. Funding may be used to acquire landscape parcels, scenic easements, or farmland preservation easements on land abutting or within the viewshed of Route 57, as well as to advance landscape, pedestrian safety and operational improvements within the towns and villages in the corridor. This program will benefit Smart Growth in the corridor.

COUNTY: Warren  
 MUNICIPALITY: Various  
 MILEPOSTS: 0 - 21.10  
 STRUCTURE NO.: N/A  
 LEGISLATIVE DISTRICT: 23 SPONSOR: NJDOT  
 PROGRAM CATEGORY: Quality of Life - Transportation Enhancements

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
NJTPA	ERC	STATE	\$100,000	\$100,000	\$100,000	\$100,000	\$100,000

**FY 2008-11**  
**STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM**  
**New Jersey Department of Transportation Projects**

<i>PROJECT NAME</i>	<i>Project ID No.</i>	<i>TIP No.</i>
Route 57, CR 519 Intersection Improvement	97062B	97062B

The project may include the addition of left and right turning lanes at each approach to the intersection. Two structures may also be included within this project. This project will be designed to be bicycle/pedestrian compatible.

The following special Federal appropriation was allocated to this project. FY 2004/Section 115/H17 \$1,300,000 (balance available \$1,300,000) and FY06 SAFETEA-LU/HPP, \$2,160,000 (available 20% per year).

COUNTY: Warren

MUNICIPALITY: Lopatcong Twp.

MILEPOSTS: 1.30 - 1.70

STRUCTURE NO.: 2101031 2105152

LEGISLATIVE DISTRICT: 23

SPONSOR: NJDOT

PROGRAM CATEGORY: Congestion Relief - Hwy Operational Improvements

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
NJTPA	PD	DEMO	\$1,300,000				
NJTPA	PD	HPP20	\$1,728,000				

**FY 2008-11**

**STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM**

**New Jersey Department of Transportation Projects**

<i>PROJECT NAME</i>	<i>Project ID No.</i>	<i>TIP No.</i>
<b>Route 80, Eastbound, West of Hope-Johnsonburg Road to East of Ledgewood Avenue, Resurfacing</b>	<b>06410</b>	<b>06410</b>

The existing roadway typically consists of three to four 12-foot asphalt concrete travel lanes with 12-foot asphalt concrete shoulders. The opposing traffic is separated by a woods and a grass median. The roadway condition is generally poor, consistently exhibiting rutting, high severity wheel path fatigue cracking, and localized patching. The outside shoulder is generally in fair to poor condition. It is proposed to mill and resurface the entire roadway with Superpave hot mix asphalt. All inlets and other roadway utility hardware will be adjusted to final grade. Raised pavement markers will be reinstalled. Deteriorated curb and curb with existing low reveal will be reconstructed. No utility work is anticipated. Only resurfacing and incidentals required to facilitate the resurfacing as outlined in the scope of work for 3R projects will be done.

Bridge decks within the project limits do not require rehabilitation; therefore, pavement will be transitioned to meet the bridge decks. A minimum vertical under clearance of 16 feet will be maintained at all underpasses with the exception of Structure 1427150 which will be at 15 feet, 8 inches.

COUNTY: Warren Sussex Morris

MUNICIPALITY: Various

MILEPOSTS: 12.80 - 28.50

STRUCTURE NO.: N/A

LEGISLATIVE DISTRICT: 23 24 25 SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Highway Resurfacing

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
NJTPA	CON	STATE		\$22,800,000			

**FY 2008-11**

**STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM**

**New Jersey Department of Transportation Projects**

<i>PROJECT NAME</i>	<i>Project ID No.</i>	<i>TIP No.</i>
<b>Route 80, Truck Weigh Station, Eastbound, Knowlton Township</b>	285A	285A

This project will provide for the upgrade of the existing truck weigh station in Knowlton Township. Proposed improvements will provide upgraded weighing equipment (weigh-in-motion scale and automated internal directional signals, 70 foot long three-platform static scale, truck weight monitoring system and a closed-circuit television system) and support facilities that will enable New Jersey State Police to more effectively perform their duties in enforcing truck weight and safety regulations. Other improvements will include advanced warning signing as well as extending the acceleration/deceleration lanes on I-80. Only five truck parking spaces will be provided in order to contain the facility within existing right of way.

COUNTY: Warren

MUNICIPALITY: Knowlton Twp.

MILEPOSTS: 1.55 - 2.75

STRUCTURE NO.: N/A

LEGISLATIVE DISTRICT: 23

SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Truck Size and Weight Control

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
NJTPA	DES	I-MAINT	\$2,000,000				
NJTPA	CON	I-MAINT				\$11,298,000	

**FY 2008-11**  
**STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM**  
**New Jersey Department of Transportation Projects**

<i>PROJECT NAME</i>	<i>Project ID No.</i>	<i>TIP No.</i>
<b>Route 80, West of Knowlton Road to West of Hope Johnsonburg Road</b>	06409	06409

The existing roadway typically consists of three or four 12-foot asphalt concrete travel lanes with 12-foot asphalt concrete outside shoulders. The opposing traffic is separated by a woods and a grass median for the majority of the project. The roadway condition is generally poor, consistently exhibiting rutting, high severity wheel path fatigue cracking, and localized patching. The outside shoulder is generally in fair to poor condition. It is proposed to mill and resurface the entire roadway with Superpave hot mix asphalt. All inlets and other roadway utility hardware will be adjusted to final grade. Raised pavement markers will be reinstalled. Deteriorated curb and curb with existing low reveal will be reconstructed. No utility work is anticipated. Only resurfacing and incidentals required to facilitate the resurfacing as outlined in the scope of work for 3R projects will be done.

Bridge decks within the project limits do not require rehabilitation; therefore, pavement will be transitioned to meet the bridge decks. A minimum vertical under clearance of 16 feet will be maintained at all underpasses.

COUNTY: Warren

MUNICIPALITY: Knowlton Twp. Blairstown Twp. Hope Twp.

MILEPOSTS: 8.00 - 12.80

STRUCTURE NO.: N/A

LEGISLATIVE DISTRICT: 23

SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Highway Resurfacing

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
NJTPA	CON	STATE	\$16,120,000				

**FY 2008-11**

**STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM**

**New Jersey Department of Transportation Projects**

<i>PROJECT NAME</i>	<i>Project ID No.</i>	<i>TIP No.</i>
<b>Route 80, Westbound, West of Hope-Johnsonburg Road to East of Ledgewood Avenue, Resurfacing</b>	<b>06411</b>	<b>06411</b>

The existing roadway typically consists of three to four 12-foot asphalt concrete travel lanes with 12-foot asphalt concrete shoulders. The opposing traffic is separated by a woods and a grass median. The roadway condition is generally poor, consistently exhibiting rutting, high severity wheel path fatigue cracking, and localized patching. The outside shoulder is generally in fair to poor condition. It is proposed to mill and resurface the entire roadway with Superpave hot mix asphalt. All inlets and other roadway utility hardware will be adjusted to final grade. Raised pavement markers will be reinstalled. Deteriorated curb and curb with existing low reveal will be reconstructed. No utility work is anticipated. Only resurfacing and incidentals required to facilitate the resurfacing as outlined in the scope of work for 3R projects will be done.

Bridge decks within the project limits do not require rehabilitation with the exception of Structure 1427154; therefore, pavement will be transitioned to meet the bridge decks. A minimum vertical under clearance of 16 feet will be maintained at all underpasses with the exception of Structure 1427150 which will be at 15 feet, 8 inches.

COUNTY: Warren Sussex Morris

MUNICIPALITY: Various

MILEPOSTS: 12.80 - 28.50

STRUCTURE NO.: N/A

LEGISLATIVE DISTRICT: 23 24 25 SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Highway Resurfacing

MPO	Phase	Fund	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012
NJTPA	CON	STATE		\$18,450,000			