

**FY 2004 TRANSPORTATION CAPITAL PROGRAM
New Jersey Department of Transportation Projects**

<i>ROUTE/PROGRAM</i>		<i>Project ID Number</i>
78	6J 6K, Truck Weigh Stations (eastbound and westbound)	860

This project, which is approximately 1.6 miles in length, will provide state-of-the-art truck weigh and inspection facilities on both the eastbound and westbound directions of I-78. The project's limits are approximately milepost 5.7 to 7.3 and the total acreage will be approximately 60 acres. Components of the project include weigh-in-motion scales, static scales, internal weigh station roadways, a control building on the eastbound side and a scale house on the westbound side. Commercial vehicle inspection buildings will be provided on both sides. The project will include significant roadway and structural improvements also. Acceleration and deceleration lanes will be provided in both direction for the weigh stations. The entire length of the project will be resurfaced in both directions using a noise reducing pavement. The New Village Road bridge over I-78 will be replaced and shifted to improve the alignment of New Village Road. The new bridge will be similar to the existing bridge as it will carry one 12-foot lane and a 1-foot shoulder in each direction and provide a sidewalk on one side, however it will be longer to accommodate the acceleration/deceleration lanes on I-78. The I-78 mainline structures over the Musconetcong River will be widened and re-decked to accept the acceleration/deceleration lanes and the inside shoulder will be brought up to standards. There are no design exceptions in this project.

This is a multi-year funded project under the provisions of Section 13 of P.L. 1995, c.108.

COUNTY: Warren

MUNICIPALITY: Greenwich Twp.

MILEPOSTS: 4.10 - 7.00

STRUCTURE NO.: 2113159 2113158 2113160

LEGISLATIVE DISTRICT: 23

SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Truck Size and Weight Control

MPO	Item No.	Phase	Fund	Amount
NJTPA	1	CON	I-MAINT	\$27,700,000

**FY 2004 TRANSPORTATION CAPITAL PROGRAM
New Jersey Department of Transportation Projects**

<i>ROUTE/PROGRAM</i>	<i>Project ID Number</i>
78 Resurfacing, Potterstown Road to I-287	00374A

This project will provide for the resurfacing of I-78 both eastbound and westbound from mileposts 23.10 to 30.80. In addition, the acceleration and deceleration lanes within the limits of the project will be lengthened to meet current standards, an outside shoulder will be added adjacent to the acceleration and deceleration lanes and all substandard guiderail will be upgraded to meet current safety standards.

The following structures are in need of patching and resurfacing; however, it is currently unclear which structures will be addressed under this project: 1018173, 1018175, 1018176, 1018151, 181612, 1816153, 1816154, 1816155, 1816157, 1816158, 1817150, 1817151, 1817152, 1817153, 1817154.

This is a multi-year funded project under the provisions of Section 13 of P.L. 1995, c.108.

COUNTY: Hunterdon Somerset

MUNICIPALITY: Readington Twp. Tewksbury Twp. Bedminster Twp.

MILEPOSTS: 23.10 - 30.80

STRUCTURE NO.: Various (See Descript.)

LEGISLATIVE DISTRICT: 23 24 16 SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Highway Resurfacing

MPO	Item No.	Phase	Fund	Amount
NJTPA	285	CON	STATE	\$4,000,000