

(DOUBLEWAL)

ISSUED: 2009

PLATE
3.4-10

[illegible]

TYPICAL SECTION
(FILL)

PREFABRICATED MODULAR WALL

- (1) THE LIMIT OF COMMON STRUCTURE VOLUME BEHIND THE WALL SHALL BE GOVERNED BY THE WIDEST LIMIT OF ALTERNATE WALL ALLOWED IN THE CONTRACT AT THAT LOCATION. THE DESIGNER SHALL CONTACT THE WALL MANUFACTURER TO DETERMINE THE WIDTH OF THE NEEDED CUT.
- (2) DRAINAGE REQUIREMENTS SHOULD BE ADDRESSED.
- (3) PAYMENT FOR THIS ITEM IS BASED ON PROJECT TO PROJECT BASIS.
- (4) REFER TO THE NDOT STANDARD SPECIFICATIONS AND SECTION 17 OF THIS MANUAL FOR PERMISSIBLE BACKFILL MATERIALS AND REQUIREMENTS FOR THE PLACEMENT OF GEOTEXTILE FILTER FABRIC MATERIAL.