



SEQ. NO.	ITEM NO.	DESCRIPTION	UNIT	CONTRACT QUANTITY	PLAN SHEET TOTALS	IF AND WHERE DIRECTED	AS-BUILT QUANTITY	BHF-17(121) QUANTITY	DKAF-26(112) QUANTITY	STATE QUANTITY	DISTRIBUTION: PLAN SHEET QUANTITY																	
1	151003M	PERFORMANCE BOND AND PAYMENT BOND	L.S.	L.S.				40%	40%	20%																		
2	155009M	FIELD OFFICE TYPE C SET-UP	U	1		1		50%	30%	20%																		
3	155027M	FIELD OFFICE TYPE C MAINTENANCE	M.O.	24		24		12	7	8																		
4	202009P	EXCAVATION, UNCLASSIFIED	C.Y.	90697	90697			301	90076	320	C-2	111	C-3	223	C-9	287	X-90	9007										
BEGIN ALTERNATE GROUP ITEMS																												
ALTERNATE GROUP C - CONCRETE PIPE																												
5	601112P	15" REINFORCED CONCRETE PIPE	L.F.	112	112			112			C-2	62	C-3	50														
6	601114P	18" REINFORCED CONCRETE PIPE	L.F.	76	76			76			C-2	46	C-3	30														
7	601118P	24" REINFORCED CONCRETE PIPE	L.F.	118	118			118			C-2	78	C-3	40														
ALTERNATE GROUP M - METAL PIPE																												
8	601076P	15" CORRUGATED METAL PIPE	L.F.	112	112			112			C-2	62	C-3	50														
9	601078P	18" CORRUGATED METAL PIPE	L.F.	76	76			76			C-2	62	C-3	50														
10	601082P	24" CORRUGATED METAL PIPE	L.F.	118	118			118			C-2	78	C-3	40														
END ALTERNATE GROUP ITEMS																												
11	159003M	BREAKAWAY BARRICADES	U	25		25		15	5	5																		
12	159015M	CONSTRUCTION IDENTIFICATION SIGNS, 4' x 8'	U	2		2				2																		
13	651057P	8" DUCTILE IRON WATER PIPE, CLASS 52	L.F.	4716	4716						C-2	2608	C-3	2108														
14	701006P	2" RIGID METALLIC CONDUIT, TYPE CUG	L.F.	18500	18500						E-1	804	E-2	804	E-3	804	E-8	804	E-9	804	E-10	804	E-11	2000	E-12	4002	E-13	4002
15	701087M	FOUNDATIONS, TYPE SFT	U	3	3			3	2		E-15	1000	E-16	1000	E-17	1000	E-18	672										
16	702015M	TRAFFIC SIGNAL STANDARD, STEEL	U	3	3			2	3		E-2	2	E-9	2	E-15	1												
17	804006P	TOPSOILING, 4" THICK	S.Y.	390	390			100	100	190	E-3	2	E-9	2	E-15	1												
18	806018P	FERTILIZING AND SEEDING, TYPE F	S.Y.	38	38	38		10	10	18	C-3	200	L-1	100	L-2	50	L-3	40										
19	806006P	FERTILIZING AND SEEDING, TYPE A-3	S.Y.	390	390			100	100	190	C-3	200	L-1	100	L-2	50	L-3	40										
20	809009P	STRAW MULCHING	S.Y.	428	390	38		110	110	208	C-3	200	L-1	100	L-2	50	L-3	40										
21	811006M	LARGE DECIDUOUS TREE, 2-2 1/2" CALIPER, BAB	U	24	24			12	10	2																		
22	9999999	NO ITEM																										
23	9999999	NO ITEM																										



New Jersey Department Of Transportation  
ESTIMATE-DISTRIBUTION OF QUANTITIES

PROJECT: ROUTE 795  
ROUTE 43  
CONTRACT NO. 010010001

Individual, Firm, Partnership, etc.  
(signature) (date)  
John L. Doe

CAN 074 - ADDED SEQ. NO. COLUMN  
EDQ-1-05 - ORIGINAL SHEET