

FY 2003-05 STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM

New Jersey Department of Transportation Projects

<i>ROUTE/PROGRAM</i>	<i>Project ID No.</i>	<i>TIP No.</i>
287 24 Interchange Improvements	98376	98376

Interchange improvements at I-287 and Route 24

This project involves the widening of the Route 24 eastbound ramp and roadway approaches on I-287 southbound. The work will consist of widening the Route 24 structure (1421153) by 3.3 meters over I-287 to the minimum two-lane ramp width of 9.6 meters. The project will also provide for the widening of the approach which will require approximately 375 meters of retaining walls.

COUNTY: Morris

MUNICIPALITY: Hanover Twp.

MILEPOSTS: Rt 287: 37.9; Rt. 24: 0 - 0.9

STRUCTURE NO.: 1421153

LEGISLATIVE DISTRICT: 26

SPONSOR: NJDOT

PROGRAM CATEGORY: Congestion Management - Hwy Operational Improvements

MPO	Phase	Fund	FY 2003	FY 2004	FY 2005	FY 2006	FY 2007
NJTPA	CON	REDISTRIBUTION	\$4,965,000				

FY 2003-05 STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM

New Jersey Department of Transportation Projects

<i>ROUTE/PROGRAM</i>		<i>Project ID No.</i>	<i>TIP No.</i>
287	Truck Weigh Station, Bergen County	858	858

Southbound Truck Weigh Station, Bergen County

This project consists of construction of truck weigh and truck inspection facilities on the southbound side of I-287. It will weigh trucks destined for both I-287 southbound and NJ Route 17 southbound. The project includes weigh-in-motion scales, static weigh scales, paving, grading, drainage, utilities (relocation and new services), striping, electrical, lighting, and landscaping. The facility consists of internal roadways, approximately 40 parking stalls for trucks, twenty stalls for autos, an inspection building and pit, a control tower of approximately 10,000 square feet, salt storage barn for Local, County and State use, and expansion of the existing Mahwah composting/recycling area currently on the site. This project includes major improvements to the NJ 17/Stag Hill Road intersection including lengthening the acceleration lane onto Route 17 southbound. Stag Hill Road, between I-287 and Route 17 (less than 1 mile), will be widened to provide two eastbound lanes and one westbound lane (currently one lane each direction). A deceleration lane into and acceleration lane from the weigh station will need to be provided along I-287 southbound. The I-287 bridge over the Ramapo River will require widening to accept the acceleration lane from the weigh station.

COUNTY: Bergen

MUNICIPALITY: Mahwah Twp.

MILEPOSTS: 66.50 - 67.50

STRUCTURE NO.: 0235172 0234173

LEGISLATIVE DISTRICT: 40

SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Truck Size and Weight Control

MPO	Phase	Fund	FY 2003	FY 2004	FY 2005	FY 2006	FY 2007
NJTPA	DES	I-MAINT	\$3,000,000				
NJTPA	ROW	I-MAINT		\$8,000,000			
NJTPA	CON	TBD				\$30,000,000	