

New Jersey Turnpike Authority
Garden State Parkway
Engineering Department

Contract No.: M-107
Title: Guide Rail Maintenance and Repair Between MP 0.0 and MP 172.4

Disclaimer: The content of this file is intended for general informational purposes only. Bidders are specifically cautioned to rely only on the written contract documents issued by the New Jersey Turnpike Authority, and not on the information in this file, when submitting a bid. Any discrepancies between the information contained in this file and the written contract documents shall not provide a basis for action against New Jersey Turnpike Authority.

Revised: September 5, 2003, Addendum No. 1

Pay Item List

Item #	Description of Item	Quant.	Meas.
1	Performance Bond	1	L.S.
2	Payment Bond	1	L.S.
3	Emergency Mobilization	175	Each
4	Emergency Nighttime Mobilization	20	Each
5	Shoulder Closings	2000	Each
6	Lane Closings	500	Each
7	Ramp Detours	15	Each
8	Replace Beam Guide Rail	120000	LF
9	Replace Beam Guide Rail, Painted	500	LF
10	Reset Beam Guide Rail	2000	LF
11	Replace Rub Rail	3000	LF
12	Replace 6'-0" Guide Rail Post and Spacer Block	1500	Each
13	Replace 6'-0" Guide Rail Post and Spacer	8500	Each
14	Replace 8'-0" Guide Rail Post and Spacer Block	150	Each
15	Replace 14" Spacer Block	150	Each
16	Replace 14" Spacer	600	Each
17	Replace 12" Back-Up Plate	200	Each
18	Replace Beam Guide Rail Anchorage	200	Each
19	Repair Anchorage with Buried End	15	Each
20	Replace Anchorage Rounded End Section	100	Each
21	Repair/Install Complete Slotted Rail Terminal	125	Each
22	Replace SRT Barrier Terminal	40	Each
23	Replace First Section of SRT Rail Element, 12'-6"	125	Each
24	Remove Concrete Footing	20	Each
25	Replace Secondary Section of SRT Rail Element, 12'-6"	125	Each
26	Replace SRT 5' Tube Sleeve and Soil Plate	10	Each
27	Replace Wooden Post SRT/ET-2000, 3'-9" x 5-1/2" x 7-1/2"	125	Each
28	Replace Wooden Post, 6'-0" x 6" x 8"	100	Each
29	Replace Wooden Spacer Block, 14" x 6" x 8"	100	Each
30	Repair/Install Complete, Extruder Terminal ET-2000	25	Each
31	Replace ET-2000 Galvanized Extruder Head	5	Each
32	Replace First Section of Rail, ET-2000, 25'	15	Each
33	Replace Secondary Rail, ET-2000, 25'	15	Each
34	Replace ET-2000 4'-6" Tube Sleeve and Soil Plate	10	Each
35	Repair/Install Complete Telescoping Guide Rail End Terminal	25	Each

Pay Item List

Item #	Description of Item	Quant.	Meas.
36	Replace Dual-Faced Guide Rail	1500	LF
37	Replace Guide Rail Attachment to Structures, Type A	20	Each
38	Replace Guide Rail Attachment to Structures, Type B	20	Each
39	Replace Guide Rail Attachment to Structures, Parapets	25	Each
40	Replace Guide Rail Attachment to Structures, Obstructions	25	Each
41	Replace Terminal Connector, Painted	5	Each
42	Replace Back-Up Plate for Terminal Connector, Painted	5	Each
43	Replace Thrie Beam Terminal Connector, Painted	5	Each
44	Replace Back-Up Plate for Thrie Beam Terminal Connector, Painted	5	Each
45	Replace 6'-6" Post, Painted	15	Each
46	Replace 1' - 9½" Spacer Block, Painted	15	Each
47	Replace Thrie Beam Back-Up Plate, Painted	10	Each
48	Replace Thrie Beam Rail Element, 20" x 12'-6", Painted	10	Each
49	Replace Thrie Beam Transition Section, Painted	10	Each
50	New Construction, Install Complete Beam Guide Rail	5000	LF
51	New Construction, Install Complete Beam Guide Rail Anchorage	25	Each
52	New Construction, Install Complete Slotted Guide Rail Terminal	25	Each
53	New Construction, Install Complete Extruder Terminal	15	Each
54	New Construction, Install Complete Telescoping Guide Rail End Term	10	Each
55	Bituminous Concrete Slope Protection, 4" Thick	1000	SY
56	Bituminous Concrete Cold Patch, 50 lb. Bag	150	Each
57	Replace Guide Rail Reflector	4500	Each
58	Replace Object Marker	200	Each
59	Install New Glare Screen	350	LF
60	Repair/Replace Damaged Glare Screen	350	LF
61	Replace Glare Screen Post	50	Each
62	Repair Telescoping Guide Rail End Terminal, Minor	10	Each
63	Cellular Phone Service	1	LS
64	Control Release Terminals	350	LF
65	Control Release Terminal Anchorages	10	Unit