

Water Testing at Marie Katzenbach School for the Deaf for 2023 was done by Pace Analytical Services.

Here is a summary of the results from currently occupied areas: These samples are "first draw" samples, which means the water has been immobile for at least six hours in the plumbing.

1st draw Maximum Contaminant Levels (MCLs): Lead = 15 mg/L

Sample Location Results:

Building #3 Kitchen Sink: 201

Building #18 Staff Bathroom Sink (Room 5): 179

Jochem Center Kitchen Sink: 128

Academic Center High School Café Handwash Station: 122

Academic Center Room 120 Sink (Room 114): 442

Academic Center Room 115 Sink (left): 257

Academic Center Room 115 Sink (right): 71.9

Academic Center High School Art Room Sink (Room 114): 444

Residence 1 Rooms 20 and 21: 86

Residence 1 Health Center Room 2: 55.7

Clock Tower Women's Bathroom: 242

These failures may be due to a number of situations. Corrosion of plumbing and fixtures are the main culprits. Most times the problems can be rectified by replacing the faucets at the problem location.

*Information provided by:

Vincent Dombay

Pace Analytical Services

NELAP Certified Lab (NJ) No. 11005, State Certification: CT PH-0143

812 Silvia Street, Ewing, NJ 08628 Telephone: 609.737.3477