

## TAXATION BUILDING

### EXTERIOR SEALANT REPLACEMENT AND GRANITE PANEL REPAIRS



The objective of this project is to mitigate water infiltration into the building due to sealant failure at windows and concrete intersections and to reset existing granite panels that have detached from its anchorage to the building. The project scope includes replacement of all exterior joint sealants, re-alignment of existing exterior granite wall panels, and replacement of the existing steel granite support ledger with new galvanized steel.