SCOPE OF WORK

NJDOT Water Service Upgrades

Sayreville Maintenance Yard, Sayreville Twp., Middlesex County Manahawkin Maintenance Yard, Stafford Twp., Ocean County

Project No. T0709-00

STATE OF NEW JERSEY

Honorable Philip D. Murphy, Governor Honorable Tahesha L. Way, Lt. Governor

DEPARTMENT OF THE TREASURY

Elizabeth Maher Muoio, Treasurer



DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION

Thomas A. Edenbaum, Director

Date: January 29, 2025

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

TABLE OF CONTENTS

SEC'	TION	PAGE
I.	OBJECTIVE	4
II.	CONSULTANT QUALIFICATIONS	4
A.	CONSULTANT & SUB-CONSULTANT PRE-QUALIFICATIONS	
III.	PROJECT BUDGET	4
A. B. C.	CONSTRUCTION COST ESTIMATE (CCE) CURRENT WORKING ESTIMATE (CWE) CONSULTANT'S FEES	4
IV.	PROJECT SCHEDULE	5
A. B.	SCOPE OF WORK DESIGN & CONSTRUCTION SCHEDULECONSULTANT'S PROPOSED DESIGN & CONSTRUCTION SCHEDULE	5 6
V.	PROJECT SITE LOCATION & TEAM MEMBERS	6
	PROJECT SITE ADDRESS PROJECT TEAM MEMBER DIRECTORY	7 7
VI.	PROJECT DEFINITION	7
A. B.	BACKGROUNDFUNCTIONAL DESCRIPTION OF THE BUILDING/SITE	
VII.	CONSULTANT DESIGN RESPONSIBILITIES	8
2	DESIGN REQUIREMENTS Water Supply Line: Site Restoration: Staging: DESIGN MEETINGS & PRESENTATIONS EXISTING DOCUMENTATION	
VIII	I. PERMITS & APPROVALS	11
A. B.	NJ UNIFORM CONSTRUCTION CODE PLAN REVIEW AND PERMITOTHER REGULATORY AGENCY PERMITS, CERTIFICATES AND APPROVALS	11
IX.	ENERGY REBATE AND INCENTIVE PROGRAMS	14

PROJECT NAME: NJDOT Water Service Upgrades PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards PROJECT NO: T0709-00

DATE: January 29, 2025

Χ.	AL	LOWANCES	15
A.	PLAN	REVIEW AND PERMIT FEE ALLOWANCE	
1	. Per	mits:	
2	. Per	mit Costs:	
3	. App	mit Costs:plications:	
4	. Cor	nsultant Fee:	
XI.	SO	W SIGNATURE APPROVAL SHEET	16
XII.	CO	NTRACT DELIVERABLES	17
XIII	. EX	HIBITS	17
	A.	SAMPLE PROJECT SCHEDULE FORMAT	
	B.	PROJECT SITE LOCATION MAP	
	C.	PHOTOS	
	D.	DRAWINGS	

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

I. OBJECTIVE

The objective of this project is to upgrade the water service connection between the water main in the street and the maintenance buildings at the NJDOT (Department of Transportation) Manahawkin Maintenance Yard and Sayreville Maintenance Yard to a minimum 2.5-inch diameter line. The upgrades are required to increase the flow rate to the buildings so that the water tanks on the new street sweepers and vacuum trucks operated by the DOT can be filled quicker thereby improving the efficiency of providing roadway maintenance operations by the DOT.

II. CONSULTANT QUALIFICATIONS

A. CONSULTANT & SUB-CONSULTANT PRE-QUALIFICATIONS

The Consultant shall be a firm pre-qualified with the Division of Property Management & Construction (DPMC) in the following discipline(s):

• P005 Civil Engineering

As well as, <u>any and all</u> other Architectural, Engineering and Specialty Disciplines necessary to complete the project as described in this Scope of Work (SOW).

III. PROJECT BUDGET

A. CONSTRUCTION COST ESTIMATE (CCE)

The initial Construction Cost Estimate (CCE) for this project is \$275,000.

The Consultant shall review this Scope of Work and provide a narrative evaluation and analysis of the accuracy of the proposed project CCE in its technical proposal based on its professional experience and opinion.

B. CURRENT WORKING ESTIMATE (CWE)

The Current Working Estimate (CWE) for this project is \$416,625.

The CWE includes the construction cost estimate and all consulting, permitting and administrative fees.

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

The CWE is the client agency's financial budget based on this project Scope of Work and shall not be exceeded during the design and construction phases of the project unless DPMC approves the change in Scope of Work through a Contract amendment.

C. CONSULTANT'S FEES

The construction cost estimate for this project *shall not* be used as a basis for the Consultant's design and construction administration fees. The Consultant's fees shall be based on the information contained in this Scope of Work document and the observations made and/or the additional information received during the pre-proposal meeting.

IV. PROJECT SCHEDULE

A. SCOPE OF WORK DESIGN & CONSTRUCTION SCHEDULE

The following schedule identifies the estimated design and construction phases for this project and the estimated durations.

ESTIMATED DURATION (Calendar Days) PROJECT PHASE 1. Site Access Approvals & Schedule Design Kick-off Meeting 14 42 2. Design Development Phase 14 Project Team & DPMC Plan/Code Unit Review & Comment 3. Final Design Phase 42 14 Project Team & DPMC Plan/Code Unit Review & Approval 7 4. Final Design Re-Submission to Address Comments 14 Project Team & DPMC Plan/Code Unit Review & Approval 5. DCA Submission Plan Review **30** 6. Permit Application Phase 7 Issue Plan Release 7. Bid Phase 42 8. Award Phase 28 9. Construction Phase 180 10. Project Close Out Phase **30**

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

B. CONSULTANT'S PROPOSED DESIGN & CONSTRUCTION SCHEDULE

The Consultant shall submit a project design and construction schedule with its technical proposal that is similar in format and detail to the schedule depicted in **Exhibit 'A'**. The schedule developed by the Consultant shall reflect its recommended project phases, phase activities, activity durations.

A written narrative shall also be included with the technical proposal explaining the schedule submitted and the reasons why and how it can be completed in the time frame proposed by the Consultant.

This schedule and narrative will be reviewed by the Consultant Selection Committee as part of the evaluation process and will be assigned a score commensurate with clarity and comprehensiveness of the submission.

V. PROJECT SITE LOCATION & TEAM MEMBERS

A. PROJECT SITE ADDRESS

The location of the project site is:

NJDOT Sayreville Maintenance Yard 49 Melrose Avenue Sayreville, Middlesex County, NJ 08872 GPS Coordinates: 40.489731° N, 74.299505° W

NJDOT Manahawkin Maintenance Yard 123 Grassy Hollow Road Manahawkin, Ocean County, NJ 08005 GPS Coordinates: 39.69451178° N, 74.26486765° W

See Exhibit 'B' for the project site location map.

2 Ioi une project site rocuitor inter-

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

B. PROJECT TEAM MEMBER DIRECTORY

The following are the names, addresses, and phone numbers of the Project Team members.

1. **DPMC Representative:**

Name: Vijay Gandhi, Project Manager

Address: <u>Division of Property Management</u> & Construction

20 West State Street, 3rd Floor

Trenton, NJ 08608-1206

Phone No: (609) 256-0031

E-Mail: Vijay.Gandhi@treas.ni.gov

2. New Jersey Department of Transportation:

Name: Sagar Rana, Project Manager

Address: P.O. Box 600

1035 Parkway Avenue

Trenton, NJ 08625

Phone No: (609) 963-2731

E-Mail: Sagar.Rana@dot.nj.gov

VI. PROJECT DEFINITION

A. BACKGROUND

The New Jersey Department of Transportation owns and operates many garage and maintenance facilities to provide storage for equipment and materials used in DOT maintenance and roadway construction operations. Additionally, specified locations area equipped to provide the service and repair for NJDOT and other agency vehicles (Based on assigned vehicle service location).

The water piping supply to the maintenance building located at the NJDOT facility in Sayreville and Manahawkin have significant delays in filling the water tanks utilized for the new road sweepers and road cleaning trucks used by the roadway maintenance operations. The water supply lines will be evaluated and upgraded to increase the flow rate to the buildings allowing the water tanks on the new street cleaning equipment to be filled quicker. This will improve the efficiency of the roadway maintenance operations used by the DOT.

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

B. FUNCTIONAL DESCRIPTION OF THE BUILDING/SITE

The NJDOT Maintenance and Yard at both the Sayreville and Manahawkin location include an Office & Garage building, outdoor yard site, Material and Storage building, and a Salt Storage Dome/Shed. The DOT facilities have variation in the property size and building layout of each of the locations.

VII. CONSULTANT DESIGN RESPONSIBILITIES

A. DESIGN REQUIREMENTS

1. Water Supply Line:

The Design Consultant shall provide the Design, Construction Administration, Permitting, and Bid/Award services to replace and upgrade the domestic water piping from the nearest public water main to each of the specified NJDOT buildings located at the Sayreville Maintenance Yard and the Manahawkin Maintenance Yard. (See **Exhibit 'C'** Photos). The Consultant shall verify the water supply line with the water service provider.

The Consultant shall provide the design and specifications to replace an approximate 150-foot distance of water supply piping from the water main to the specified location the DOT building at each of the facilities. The new 2.5-inch diameter water supply line will replace the possibly existing 1.0-inch diameter supply line at Sayreville Maintenance Facility. The new 2.5-inch diameter water supply line will replace the possibly existing 1.5-inch supply line at Manahawkin Maintenance Facility. Although past drawings are attached in 'Exhibit D', the Consultant should verify the current size and location of the water supply lines from the main supply to the desired location of the maintenance building. Furthermore, the Consultant must incorporate the design and placement of a water supply spigot, along with the necessary adapters and fittings, as approved by the Agency. These components should be compatible with the hose diameter of the water tanks connected to the street sweepers. For instance, the Manahawkin Maintenance Facility requires a V-shaped spigot splitter with openings measuring 1.0-inch and 4.0-inches in diameter.

The design documents shall include all related equipment, including but not limited to, temporary utilities and facilities, piping, valves, hydrants, outlets, controls, backflow preventers, and meters.

The Consultant shall coordinate any necessary installation specifications with the water service utility provider at each of the following DOT Facilities:

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

Sayreville Maintenance Facility

Borough of Sayreville Water and Sewer Utilities 167 Main Street Sayreville NJ 08872

Phone: (732) 390-7060

Email: water@sayreville.com

Manahawkin Maintenance Facility

Stafford Township Water & Sewer 260 East Bay Avenue
Manahawkin, NJ 08050

Phone: (609) 597-1000 Ext. 8590

The design documents shall identify the existing underground utility line locations, sizes, and elevations of critical crossing points that will be impacted by this upgrade such as underground utilities shall include items such as: fire and domestic water, steam, gas, storm, sewer, fiber optic, cable, and telephone lines, manholes, basin and inlet connections, utility chambers and tunnels, etc. This information shall be used to document their locations on the design drawings and prevent utility line interference, excavation accidents, utility disruption or shutdown during the installation and tie-in of the new lines to the existing utility infrastructure.

All "on site" underground utility survey information and previous "on site" underground utility survey reports supplied by the Client Agency or DPMC shall be provided as part of this upgrade and must be field verified and confirmed with line detection methods by the Consultant.

The Consultant shall anticipate the costs necessary to update these documents to obtain the appropriate underground utility information and include that amount in the base bid of their fee proposal.

All replaced water supply lines shall be appropriately tested for pressure, leaks, etc.

2. Site Restoration:

The design documents shall identify the Agency approved site restoration work needed after installation of the lines including roadways, driveways, parking lots, sidewalks, and lawn areas.

3. Staging:

Construction documents shall include a staging area approved by the Project Team indicating the location where the contractor can store debris, materials, tools, and equipment.

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

B. DESIGN MEETINGS & PRESENTATIONS

1. Design Meetings:

Conduct the appropriate number of review meetings with the Project Team members during each design phase of the project so they may determine if the project meets their requirements, question any aspect of the contract deliverables, and make changes where appropriate. The Consultant shall describe the philosophy and process used in the development of the design criteria and the various alternatives considered to meet the project objectives. Selected studies, sketches, cost estimates, schedules, and other relevant information shall be presented to support the design solutions proposed. Special considerations shall also be addressed such as: Contractor site access limitations, utility shutdowns and switchover coordination, phased construction and schedule requirements, security restrictions, available swing space, material and equipment delivery dates, etc.

It shall also be the responsibility of the Consultant to arrange and require all critical Sub-Consultants to be in attendance at the design review meetings.

Record the minutes of each design meeting and distribute within three (3) calendar days to all attendees and those persons specified to be on the distribution list by the Project Manager.

2. Design Presentations:

The minimum number of design presentations required for each phase of this project is identified below for reference:

Design Development Phase: One (1) oral presentation at phase completion.

Final Design Phase: One (1) oral presentation at phase completion.

C. EXISTING DOCUMENTATION

Copies of the following documents will be provided to each Consulting firm at the pre-proposal meeting to assist in the bidding process.

- Boundary and Topographic Survey: N.J. Department of Transportation Maintenance Facility Site: 9/6/1994, Edwards and Kelcey, Inc.
- DPMC Project T0545-00: Double-Wide Office Trailer Installation: 10/9/15, McAuliffe & Carroll Architects, LLC.
- DPMC Project T0545-00: Office Building: 7/13/15, Pennell Land Surveying, Inc.
- DPMC Project T0449-1: Crew Restroom Trailer Installation NJDOT Manahawkin Maintenance Facility: May 15, 2007

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

Review these documents and any additional information that may be provided at a later date such as reports, studies, surveys, equipment manuals, as-built drawings, etc. The State does not attest to the accuracy of the information provided and accepts no responsibility for the consequences of errors by the use of any information and material contained in the documentation provided. It shall be the responsibility of the Consultant to verify the contents and assume full responsibility for any determination or conclusion drawn from the material used. If the information provided is insufficient, the Consultant shall take the appropriate actions necessary to obtain the additional information required.

All original documentation shall be returned to the provider at the completion of the project.

VIII. PERMITS & APPROVALS

A. NJ UNIFORM CONSTRUCTION CODE PLAN REVIEW AND PERMIT

The project construction documents must comply with the latest adopted edition of the NJ Uniform Construction Code (NJUCC).

The latest NJUCC Adopted Codes and Standards can be found at:

http://www.state.nj.us/dca/divisions/codes/codreg/

1. NJ Uniform Construction Code (NJUCC) Plan Review

Consultant shall estimate the cost of the NJUCC Plan Review by DCA and include that amount in their fee proposal line item entitled "Plan Review and Permit Fee Allowance", refer to paragraph X.A.

Upon approval of the Final Design Phase Submission by DPMC, the Consultant shall submit the construction documents to the Department of Community Affairs (DCA), Bureau of Construction Project Review to secure a complete plan release.

As of July 25, 2022, the Department of Community Affairs (DCA) is only accepting digital signatures and seals issued from a third party certificate authority.

Procedures for submission to the DCA Plan Review Unit can be found at:

https://www.state.nj.us/dca/divisions/codes/forms/pdf_bcpr/pr_app_guide.pdf

Consultant shall complete the "Project Review Application" and include the following on Block 5 as the "Owner's Designated Agent Name":

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

Trevor M. Dittmar, DPMC PO Box 235 Trenton, NJ 08625-0235 Trevor.Dittmar@treas.nj.gov 609-984-5529

The Consultant shall complete the NJUCC "Plan Review Fee Schedule", determine the fee due and pay the NJUCC Plan Review fees, refer to Paragraph X.A.

The NJUCC "Plan Review Fee Schedule" can be found at:

http://www.state.nj.us/dca/divisions/codes/forms/pdf bcpr/pr fees.pdf

2. NJ Uniform Construction Code Permit

Upon receipt of a complete plan release from the DCA Bureau of Construction Project Review, the Consultant shall complete the NJUCC permit application and all applicable technical subcode sections. The "Agent Section" of the application and certification section of the building sub-code section shall be signed. These documents, with **six** (6) **sets of DCA approved, signed and sealed construction documents** shall be forwarded to the DPMC Project Manager. The Consultant may obtain copies of all NJUCC permit applications at the following website:

https://www.nj.gov/dca/divisions/codes/resources/constructionpermitforms.html

All other required project permits shall be obtained and paid for by the Consultant in accordance with the procedures described in Paragraph VIII.B.

3. Prior Approval Certification Letters:

The issuance of a construction permit for this project may be contingent upon acquiring various "prior approvals" as defined by N.J.A.C. 5:23-1.4. It is the Consultant's responsibility to determine which prior approvals, if any, are required. The Consultant shall submit a general certification letter to the DPMC Plan & Code Review Unit Manager during the Permit Phase of this project that certifies all required prior approvals have been obtained.

In addition to the general certification letter discussed above, the following specific prior approval certification letters, where applicable, shall be submitted by the Consultant to the DPMC Plan & Code Review Unit Manager: Soil Erosion & Sediment Control, Water & Sewer Treatment Works Approval, Coastal Areas Facilities Review, Compliance of Underground Storage Tank Systems with N.J.A.C. 7:14B, Pinelands Commission, Highlands Council, Well Construction and Maintenance; Sealing of Abandoned Wells with N.J.A.C. 7:9D, Certification that all utilities have been disconnected from structures to be demolished, Board of Health Approval for Potable Water Wells, Health Department Approval for Septic Systems. It shall be

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

noted that in accordance with N.J.A.C. 5:23-2.15(a)5, a permit cannot be issued until the letter(s) of certification is received.

4. Multi-building or Multi-site Permits:

A project that involves many buildings and/or sites requires that a separate permit shall be issued for each building or site. The Consultant must determine the construction cost estimate for *each* building and/or site location and submit that amount where indicated on the permit application.

5. Special Inspections:

In accordance with the requirements of the New Jersey Uniform Construction Code N.J.A.C. 5:23-2.20(b), Bulletin 03-5 and Chapter 17 of the International Building Code, the Consultant shall be responsible for the coordination of all special inspections during the construction phase of the project.

Bulletin 03-5 can be found at:

http://www.state.nj.us/dca/divisions/codes/publications/pdf_bulletins/b_03_5.pdf

a. Definition:

Special inspections are defined as an independent verification by a certified special inspector for **Class I buildings and smoke control systems in any class building**. The special inspector is to be independent from the Contractor and responsible to the Consultant so that there is no possible conflict of interest.

Special inspectors shall be certified in accordance with the requirements in the New Jersey Uniform Construction Code.

b. Responsibilities:

The Consultant shall submit with the permit application, a list of special inspections and the agencies or special inspectors that will be responsible to carry out the inspections required for the project. The list shall be a separate document, on letter head, signed and sealed.

B. OTHER REGULATORY AGENCY PERMITS, CERTIFICATES AND APPROVALS

The Consultant shall identify and obtain all other State Regulatory Agency permits, certificates, and approvals that will govern and affect the work described in this Scope of Work. An itemized list of these permits, certificates, and approvals shall be included with the Consultant's Technical Proposal and the total amount of the application fees should be entered in the Fee Proposal line item entitled, "Plan Review and Permit Fee Allowance."

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

The Consultant may refer to the Division of Property Management and Construction "Procedures for Architects and Engineers Manual", Paragraph "9. REGULATORY AGENCY APPROVALS" which presents a compendium of State permits, certificates, and approvals that may be required for this project.

The Consultant shall determine the appropriate phase of the project to submit the permit application(s) in order to meet the approved project milestone dates.

Where reference to an established industry standard is made, it shall be understood to mean the most recent edition of the standard unless otherwise noted. If an industry standard is found to be revoked, or should the standard have undergone substantial change or revision from the time that the Scope of Work was developed, the Consultant shall comply with the most recent edition of the standard.

IX. ENERGY REBATE AND INCENTIVE PROGRAMS

The Consultant shall review any and all programs on the State and Federal level to determine if any proposed upgrades to the mechanical and/or electrical equipment and systems for this project qualify for approved rebates and incentives.

The Consultant shall review the programs available on the "New Jersey's Clean Energy Program" website at: http://www.njcleanenergy.com as well as federal websites and New Jersey electric and gas utility websites to determine if and how they can be applied to this project.

The Consultant shall identify all applicable rebates and incentives in their technical proposal and throughout the design phase.

The Consultant shall be responsible to complete the appropriate registration forms and applications, provide any applicable worksheets, manufacturer's specification sheets, calculations, attend meetings, and participate in all activities with designated representatives of the programs and utility companies to obtain the entitled financial incentives and rebates for this project.

All costs associated with this work shall be estimated by the Consultant and the amount included in the base bid of its fee proposal.

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

X. ALLOWANCES

A. PLAN REVIEW AND PERMIT FEE ALLOWANCE

The Consultant shall obtain and pay for all of the project permits in accordance with the guidelines identified below.

1. Permits:

The Consultant shall determine the various permits, certificates, and approvals required to complete this project.

2. Permit Costs:

The Consultant shall estimate the application fee costs for all of the required project permits, certificates, and approvals (excluding the NJ Uniform Construction Code permit) and include that amount in its fee proposal line item entitled "Plan Review and Permit Fee Allowance". A breakdown of each permit and application fee shall be attached to the fee proposal for reference. NOTE: The NJ Uniform Construction Code permit is excluded since it will be paid for by the State.

3. Applications:

The Consultant shall complete and submit all permit applications to the appropriate permitting authorities and the costs shall be paid from the Consultant's permit fee allowance. A copy of the application(s) and the original permit(s) obtained by the Consultant shall be given to the DPMC Project Manager for distribution during construction.

4. Consultant Fee:

The Consultant shall determine what is required to complete and submit the permit applications, obtain supporting documentation, attend meetings, etc., and include the total cost in the base bid of its fee proposal under the "Permit Phase" column.

Any funds remaining in the permit allowance will be returned to the State at the close of the project.

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

XI. SOW SIGNATURE APPROVAL SHEET

This Scope of Work shall not be considered a valid document unless all signatures appear in each designated area below.

The client agency approval signature on this page indicates that they have reviewed the design criteria and construction schedule described in this project Scope of Work (including the subsequent contract deliverables and exhibits) and verifies that the work will not conflict with the existing or future construction activities of other projects at the site.

SOW PREPARED BY:		1/29/2025
	ALISON F. GOTTLIEB, PROJECT MANAGER DPMC PROJECT PLANNING & INITIATION	DATE
SOW APPROVED BY:		1/29/2025
	JAMES WRIGHT, MANAGER DPMC PROJECT PLANNING & INITIATION	DATE
SOW APPROVED BY:		1/30/2025
	DENNIS W. MESZAROS, EXECUTIVE MANAGER NEW JERSEY DEPARTMENT OF TRANSPORTATION	DATE N
SOW APPROVED BY:		01/31/2025
	VIJAY GANDHI, PROJECT MANAGER DPMC PROJECT MANAGEMENT GROUP	DATE
SOW APPROVED BY:	Jeanette M. Barrard JEANETTE M. BARNARD, DEPUTY DIRECTOR	3.6.25 DATE
	DIV PROPERTY MGT & CONSTRUCTION	DAIL

PROJECT LOCATION: Manahawkin & Sayreville Maintenance Yards

PROJECT NO: T0709-00 DATE: January 29, 2025

XII. CONTRACT DELIVERABLES

The following are checklists listing the Contract Deliverables that are required at the completion of each phase of this project. The Consultant shall refer to the DPMC publication entitled "Procedures for Architects and Engineers," 3.0 Edition, dated September 2022 available at https://www.nj.gov/treasury/dpmc/Assets/Files/ProceduresforArchitectsandEngineers.pdf for a detailed description of the deliverables required for each submission item listed. References to the applicable paragraphs of the "Procedures for Architects and Engineers" are provided.

Note that the Deliverables Checklist may include submission items that are "S.O.W. Specific Requirements". These requirements will be defined in the project specific scope of work and included on the deliverables checklist.

This project includes the following phases with the deliverables noted as "Required by S.O.W" on the Deliverables Checklist:

- DESIGN DEVELOPMENT PHASE
- FINAL DESIGN PHASE
- PERMIT APPLICATION PHASE
- BIDDING AND CONTRACT AWARD
- CONSTRUCTION PHASE
- PROJECT CLOSE-OUT PHASE

XIII. EXHIBITS

- A. SAMPLE PROJECT SCHEDULE FORMAT
- B. PROJECT SITE LOCATION MAP
- C. PHOTOS
- D. DRAWINGS

END OF SCOPE OF WORK

Deliverables Checklist Design Development Phase

A/E Name:

A/E Manual	Submission Item		Required by S.O.W.		Previously Submitted		osed
Reference		Yes	No	Yes	No	Yes	No
14.4.1.	A/E Statement of Site Visit						
14.4.2.	Narrative Description of Project						
14.4.3.	Building Code Information Questionnaire						
14.4.4.	Space Analysis						
14.4.5.	Special Features						
14.4.6.	Catalog Cuts						
14.4.7.	Site Evaluation						
14.4.8.	Subsurface Investigation						
14.4.9.	Surveys						
14.4.10.	Arts Inclusion						
14.4.11.	Design Rendering						
14.4.12.	Regulatory Approvals						
14.4.13.	Utility Availability						
14.4.14.	Drawings (6 Sets)						
14.4.15.	Specifications (6 Sets)						
14.4.16.	Current Working Estimate/Cost Analysis						
14.4.17.	Project Schedule						
14.4.18.	Formal Presentation						
14.4.19.	Plan Review/Scope of Work Compliance Statement						
14.4.20.	Design development Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						
							<u> </u>
							
							

his checklist shall be completed by the Design Consultant and included as the cover sheet of this submission to
locument to the DPMC the status of all the deliverables required by the project specific Scope of Work.
dealine to the Britie the status of all the deliverables required by the project specific scope of Work.

Date

Consultant Signature

Deliverables Checklist Final Design Phase

A/E Name:

A/E Manual	Submission Item	Requi	red by .W.	Previously Submitted		Encl	osed
Reference		Yes	No	Yes	No	Yes	No
15.4.1.	A/E Statement of Site Visit						
15.4.2.	Narrative Description of Project						
15.4.3.	Building Code Information Questionnaire						
15.4.4.	Space Analysis						
15.4.5.	Special Features						
15.4.6.	Catalog Cuts						
15.4.7.	Site Evaluation						
15.4.8.	Subsurface Investigation						
15.4.9.	Surveys						
15.4.10.	Arts Inclusion						
15.4.11.	Design Rendering						
15.4.12.	Regulatory Approvals						
15.4.13.	Utility Availability						
15.4.14.	Drawings (6 Sets)						
15.4.15.	Specifications (6 Sets)						
15.4.16.	Current Working Estimate/Cost Analysis						
15.4.17.	Project Schedule						
15.4.18.	Formal Presentation						
15.4.19.	Plan Review/Scope of Work Compliance						
	Statement						
15.4.20.	Final Design Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						

hall be completed by the Design Consultane DPMC the status of all the deliverables				ssion to
Consultant Signature		 Date	 	

Deliverables Checklist Permit Application Phase

A/E Manual	Submission Item	Required by S.O.W.		Previously Submitted		Enclosed	
Reference		Yes	No	Yes	No	Yes	No
16.1.	N.J. UCC Permit Application						
16.4.	Drawings, Signed and Sealed (6 Sets)						
16.5.	Specifications, Signed and Sealed (6 Sets)						
16.6.	Current Working Estimate/Cost Analysis						
16.7.	Project Schedule						
16.8.	Plan Review/Scope of Work Compliance Statement						
16.9.	Permit Application Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements	-					
							ļ
							
	shall be completed by the Design Consultant an he DPMC Project Manager the status of all the						

Date

Consultant Signature

Deliverables Checklist Bidding and Contract Award Phase

A/E Manual	Submission Item	_	red by .W.	Previously Submitted		Enclosed	
Reference		Yes	No	Yes	No	Yes	No
17.1.1.	Notice of Advertising						
17.1.2.	Bid Proposal Form						
17.1.3.	Bid Clearance Form						
17.1.4.	Drawings (6 Sets)						
17.1.5.	Specifications (6 Sets)						
17.1.6.	Construction Schedule						
17.3	Pre-Bid Conference/Mandatory Site Visit						
17.3.1.	Meeting Minutes						
17.4	Bulletins						
17.5	Post Bid Meeting						
17.6.	Contract Award "Letter of Recommendation"						
17.8.	Bid Protests - Hearings						
17.9.	Bidding and Contract Award Phase						
	Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						
	shall be completed by the Design Consultant and he DPMC the status of all the deliverables require						sion t
	Consultant Signature			 Date			

Deliverables Checklist Construction Phase

A/E Manual	Submission Item Pre-Construction Meeting	Required by S.O.W.		Previously Submitted		Enclosed	
Reference		Yes	No	Yes	No	Yes	No
18.2.							
18.3.	Submittal Log						
18.4.	Construction Schedule						
18.5.	Project Progress Meetings						
18.7.	Contractor's Invoicing and Payment Process						
18.8.	Contractor Submittals						
18.10.	Testing						
18.11.	Shop Drawings (6 Sets)						
18.12.	As-Built & Record Set Drawings (6 Sets)						
18.13.	Change Orders						
18.14.	Construction Photographs						
18.15.	Field Observations						
18.17.	Construction Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						

shall be completed by the Design Cons he DPMC the status of all the deliveral				
Consultant Signature			Date	
מ	PAGE 22			

Deliverables Checklist Project Close-Out Phase

A/E Name:		

A/E Manual			red by		ously	Encl	osed
Reference	Submission Item	Yes	No	Yes	No	Yes	No
19.3.	Development of Punch List and Inspection Reports						
19.5.	Determination of Substantial Completion						
19.6.	Correction/Completion of Punch List						
19.7.	Submission of Close-Out Documentation						
19.7.1.	As-Built and Record Sets of Drawing (6 Sets)						
19.8.	Final Payment						
19.9.1.	Contractors Final Payment						
19.9.2.	A/E's Final Payment						
19.10.	Project Close-Out Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						
]							

This checklist shall be completed by the Design Consultant and included a document to the DPMC the status of all the deliverables required by the part of the process of th	
Consultant Signature	Date

February 7, 1997 **Rev.**: January 29, 2002

Responsible Group Code Table

The codes below are used in the schedule field "GRP" that identifies the group responsible for the activity. The table consists of groups in the Division of Property Management & Construction (DPMC), as well as groups outside of the DPMC that have responsibility for specific activities on a project that could delay the project if not completed in the time specified. For reporting purposes, the groups within the DPMC have been defined to the supervisory level of management (i.e., third level of management, the level below the Associate Director) to identify the "functional group" responsible for the activity.


CODE	DESCRIPTION	REPORTS TO ASSOCIATE DIRECTOR OF:
CM	Contract Management Group	Contract Management
CA	Client Agency	N/A
CSP	Consultant Selection and Prequalification Group	Technical Services
A/E	Architect/Engineer	N/A
PR	Plan Review Group	Technical Services
CP	Construction Procurement	Planning & Administration
CON	Construction Contractor	N/A
FM	Financial Management Group	Planning & Administration
OEU	Office of Energy and Utility Management	N/A
PD	Project Development Group	Planning & Administration

EXHIBIT 'A'

	Description	Rspu Weeks	
<proj></proj>			
Design	a.		
CV3001	Schedule/Conduct Predesign/Project Kick-Off Mtg.		
CV3020	Prepare Program Phase Submittal		
CV3021	Distribute Program Submittal for Review		
CV3027	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3022	Review & Approve Program Submittal	5	
CV3023	Review & Approve Program Submittal	84	
CV3024	Review & Approve Program Submittal	8	
CV3025	Consolidate & Return Program Submittal Comments	8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	
CV3030	Prepare Schematic Phase Submittal	## A P P P P P P P P P P P P P P P P P P	
CV3031	Distribute Schematic Submittal for Review		
CV3037	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3032	Review & Approve Schematic Submittal	**************************************	
CV3033	Review & Approve Schematic Submittal		
CV3034	Review & Approve Schematic Submittal		
CV303S	Consolidate & Return Schematic Submittal Comment		
CV3040	Prepare Design Development Phase Submittal	¥	
CV3041	Distribute D. D. Submittal for Review		
CV3047	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3042	Review & Approve Design Development Submittal		
CV3043	Review & Approve Design Development Submittal		
CV3044	Review & Approve Design Development Submittal	8	
CV3045	Consolidate & Return D.D. Submittal Comments		
CV3050	Prepare Final Design Phase Submittal	YB	
CV3051	Distribute Final Design Submittal for Review		
CV3052	Review & Approve Final Design Submittal	Y	
CV3053	Review & Approve Final Design Submittal	Œ	
CV3054	Review Final Design Submitl for Constructability	800	
NOTE:		DBCA - TEST Sheet 1 of 3	
Ref. Scoj	Refer to section "IV Project Schedule" of the Scope of Work for contract phase durations.	Bureau of Design & Construction Services	ATT 'A'
			T7 TT

The Content of the	Activity	\															ſ
A contract of the Design Submitted	A		Rspn						Weeks								
Submit Permit Application Documents CM	CV3055	Review & Approve Final Design Submittal	Æ												THE REAL PROPERTY.		THE REAL PROPERTY.
Subtrait Permit Application Documents AB Subtrait Permit Application Documents & Subtrait Permit Acquisition CM Subtrait Bidding Cost Analysis (DPMC-38) CM Subtrait Bidding Cost Cost Cost Cost Cost Cost Cost Cost	CV3056	Consolidate & Return Final Design Comments	₹										0 00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		000 E		
Contact Cont	CV3060	Prepare & Submit Permit Application Documents	AB												2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	v v	
Construction Contracts Construction Contra	CV3068	Prepare & Submit Bidding Cost Analysis (DPMC-38)	CM														1 20
Avarage Construction Contracts CA	Plan R	Review-Permit Acquisition											100				
A ward	CV4001	Review Constr. Documents & Secure UCC Permit	- BR				20 Mg	Color	Email						a ag m	· · · · ·	en o i
Id Clearance	CV4010	Provide Funding for Construction Contracts	CA		EL MAN AND AND AND AND AND AND AND AND AND A		10 10 10 10 10 10 10 10 10 10 10		* 00 0							2	- 100 FB
Award Award CP Project & Bid Construction Contracts CP Project & Bid Construction For Award CP Bids & Prp. Recommendation for Award CP Project & Bid Construction For Award CP 1 Recommendation for Award CP Project & Bid Construction For Award CP 1 Recommendation for Award CP Project & Bid Construction For Award CP 1 Recommendation for Award CP Project School For Award CP 1 Recommendation for Award CP Project School For Award CP Onstruction Stantials CM CM Lead Procurement Item Ordered CON Project School For Award 1 Work Start CON Project School For Award 2 Submit Shop Drawings CON Project School For Award 3 Work (50%-) Complete CON Project School For Award 4 Work (50%-) Complete CON Project School For Award 4 Work (50%) Complete CON Project School For Award 5 Work (50%) Complete CON Project School For Award 6 Primawara Systems, Inc. Bureau of	CV4020	Secure Bid Clearance	™							DEST							
Bids & Prep. Recommendation for Award CP Bids & Prep. Recommendation CP Bids & Prep. Recom	Adver	tise-Bid-Award															
Bids & Prep. Recommendation for Award CM Bids & Prep. Recommendation for Award CM Bids & Prep. Recommendation for Award CM onstruction Contracts/Issue NTP CM Start/Contract Work (25%) Complete COM Sconstruction Submittals COM Each Procurement Item Ordered COM Sconstruction Submittals COM Sconstruction Sub	CV5001	Advertise Project & Bid Construction Contracts	ಕಿ								2 0				* 100 miles	· · ·	
Bids & Prep. Recommendation for Award AE	CV5010	Open Construction Bids	පි		100 m 100 m										,	5	COCCES TO ACT AND AND MACHINE AND ACT OF COMME
Bids & Prep. Recommendation for Award AE onstruction Contracts/Issue NTP CP onstruction Star/Ussue NTP CM Star/Contract Work (25%) Complete CON construction Star/Ussue NTP CM Star/Contract Work (25%) Complete CON construction Meeting CON construction Submittals CON e for Longest Lead Procurement Item Ordered CON e Submit Shop Drawings CON c Submit Shop Drawings CON 3 Work (50%+) Complete CON Porture of the contract phase durations. Bureau of Design & Construction Services	CV5011	Evaluate Bids & Prep. Recommendation for Award	8		* 13 10				155			A			2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	10 Me	
Start Contract Start	CV5012	Evaluate Bids & Prep. Recommendation for Award	AE		0.00								E E E E E E E E E E E E E E E E E E E			1	27 A 63
CP CP	CV5014	Complete Recommendation for Award	ප									**************************************		10 10 mm		202	A 16 .
Start/Contract Work (25%) Complete	CV5020	Award Construction Contracts/Issue NTP	පි														
Start/Contract Work (25%) Complete	Constr	uction															
Preconstruction Meeting Begin Preconstruction Meeting Begin Preconstruction Meeting Begin Preconstruction Submittals CON Freque & Submit Shop Drawings Complete Construction Submittals CON Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (15%) Complete CON	CV6000	Project Construction Start/Issue NTP	₹											**************************************		100 to	10 mm
Preconstruction Meeting Begin Preconstruction Submittals Longest Lead Procurement Item Ordered CON Complete Construction Submittals Contract Work (30%+) Complete Contract Work (30%+) Complete Contract Work (75%) Complete Contract Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6001	Contract Start/Contract Work (25%) Complete	CON													6	
Begin Preconstruction Submittals Longest Lead Procurement Item Ordered Lad Time for Longest Lead Procurement Item Ordered Con Prepare & Submit Shop Drawings Complete Construction Submittals Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (50%) Complete Contract Work (75%) Complete Contract Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6002	Preconstruction Meeting	CM			4 A P	** ** ** ** ** ** ** ** ** ** ** **						M. Burn	FN 0	A SE SE		or to the
Longest Lead Procurement Item Ordered CON Lead Time for Longest Lead Procurement Item CON Prepare & Submit Shop Drawings Complete Construction Submittals Complete Construction Submittals Complete Construction Submittals Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6003	Begin Preconstruction Submittals	CON								TATION NO. 1	- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1-	TO BE SENTEN		TO CONTRACT OF		
Lead Time for Longest Lead Procurement Item CON Prepare & Submit Shop Drawings Complete Construction Submittals Configuration Submit Shop Drawings Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work for confract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6004	Longest Lead Procurement Item Ordered	CON								- 1000 0						
Prepare & Submit Shop Drawings Complete Construction Submittals Roughing Work Start Roughing Work Start Perform Roughing Work Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6005	Lead Time for Longest Lead Procurement Item	CON														
Complete Construction Submittals Roughing Work Start Perform Roughing Work Contract Work (50%+) Complete Contract Work (50%) Complete Contract Work (75%) Complete Contract Work (75%) Complete To section "IV Project Schedule" of the e of Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6006	Prepare & Submit Shop Drawings	CON		10 M	PERMIT	Marine Company				1 04 DE				(a)	2 (A)	119 KZ
Roughing Work Start CON Perform Roughing Work CONTract Work (30%+) Complete Contract Work (30%+) Complete CON Contract Work (75%) Complete CON Contract Work (75%) Complete CON It to section "IV Project Schedule" of the e of Work for contract phase durations. Bureau of Design & Construction Services © Primavera Systems, Inc.	CV6007	Complete Construction Submittals	CON			5 0076											T and
Perform Roughing Work Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work for contract phase durations. © Primavera Systems, Inc.	CV6011	Roughing Work Start	CON		An order or			CONTROL OF THE PARTY OF T							V 0 100 CORROLAN P 190 MAY 2 PER 1		
Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete CON Contract Work (75%) Complete CON Bureau of Design & Construction Services PBUFFAULTION PBCA-TEST Bureau of Design & Construction Services	CV6012	Perform Roughing Work	CON						274-96-27-4-4-						2 (5) 2 (5) 2 (5) 3 (5) 3 (5) 1 (5) (5)	THE REP. TO.	N N
Contract Work (75%) Complete CONTRACT DBCA - TEST Bureau of Design & Construction Services © Primavera Systems, Inc.	CV6010	Contract Work (50%+) Complete	CON								- 10-						
Contract Work (75%) Complete r to section "IV Project Schedule" of the e of Work for contract phase durations. © Primavera Systems, Inc.	CV6013	Longest Lead Procurement Item Delivered	CON														0 10 015 H3 VI 100 000
r to section "IV Project Schedule" of the e of Work for contract phase durations. © Primavera Systems, Inc.	CV6020	Contract Work (75%) Complete	CON								to enter the second of the sec				er og		\$ 145 6 1861 Ad
r to section "IV Project Schedule" of the e of Work for contract phase durations. © Primavera Systems, Inc.	NOTE		DBCA - TEST						Sheet 2 of								
© Primavera Systems, Inc.	Ref	er to section "IV Project Schedule" of the pe of Work for contract phase durations.		ureau of Desig	n & Co	nstructi	on Ser	vices			X		2		-		
		© Primavera Systems, Inc.								4	7				4	4	


Description Septimental Computer Computer Septimental Computer Comput	Activity													NA.												
Interior Finishes Surface CON Substantial Completion CON Substantial Completion Declared CON Substantial Completion Declared Completion Declared Completion Declared Completion Declared Completion Declared Completion Contract Complete Deferred Contraction Complete Completion Declared Contraction Complete Contract Contraction Contract Contraction Contract Contraction Contract Contraction Contract Completion Declared Completion Completion Declared Completion Declared Completion Declared Completion Completion Declared Declared Completion Declared Declared Declared Declared Declared D	1 0%0	Description Description	Rspn	THE STATE OF THE S	- Tanna		THE REAL PROPERTY.		CHANGE OF THE PARTY OF THE PART	HILLIAN	THE REAL PROPERTY.	THE PERSON NAMED IN COLUMN					TOTAL	ALIMENTO I	THE PERSON NAMED IN							2
Interior Finishes Start	10010	Rougning Work Complete	CON	10 0 0 10 19 10 19		A S		N 4 50		7 10 10 00 10 10 00 10 10 00 10				- 17 1					 - 1	- 6- 		100 100 100 100 100 100 100 100 100 100	2 dis		1 1	
Install merior Finishes COM Comman Work to Exbandial Completion Comman Work for Construction Complete Complete Deferred Pennel List/Seasonal Activities Complete Completion Contracts Complete Complete Completion Declared Complete Completion Declared Complete Complete Complete Complete Complet	CV6021	Interior Finishes Start	CON	on or	and the second of the second o	 	out Title Land Land of the	7 5 6 5 6 6 7 6 6 7 60	- 100 MI	or distance of								1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		me nd m		A TOTAL STATE OF THE STATE OF T	and to the state of the state o	10 10 10 10 1		20 00 0
Subtantial Completion Subtantial Completion Subtantial Completion Subtantial Completion Subtantial Completion Complete Deferred Panel List/Seasonal Activities Toyler Construction Complete Close Out Construction Complete Close Out AE Contract Completion Declared Completion	CV6022	Install Interior Finishes	CON												-			1				1				· •
Substantial Completion Declared Complete Deferred Punch List/Seasonal Activities Complete Deferred Punch List/Seasonal Activities Project Construction Complete Close Out Activities Close Out Activit	CV6030	Contract Work to Substantial Completion	CON	in i	1 March	THE RES		9 X 19			er eet 6 er eeuwen er eeuwen er e			**************************************				in an in an an in terreture an	 					in the second	o a cale	
Compilete Deferred Puriot List/Seasonal Activities CON Project Construction Compilete CM Close Out Construction Compilete CM Close Out A.B. Contracts Compilete CM Construction Compilete CM Construction Compilete CM Project Compiletion Declared CM Project Compiletion Declared CM Project Compiletion Declared CM Project Compiletion Declared CM Project Compiletion Project Schedule" of the Construction Services CM CM CM CM CM CM CM C	CV6031	Substantial Completion Declared	CM	0 0 0 0 0 0 0 0 0 0 0 0	191 W		10 10 10 10 10 10 10 10 10 10 10 10 10 1				one a c			29 R 29 R 29 M 20 M 20 M		4 2	to S. and	ender in etter en	20 00 000 20 00 000			5 # 5 5 # 5 # 5 # 5 #				
Project Construction Complete Close Out CAR Contracts Construction Complete Construction Contracts Construction Contract Project Completion Declared Construction Contract Project Completion Declared Construction Contract Construction Contract Construction Contract plase durations.	CV6075	Complete Deferred Punch List/Seasonal Activities	CON	r gran		e e e	e to di										20 20 20 20 20 20 20 20 20 20 20 20 20 2	N 27 3				2 0 0 2 0 0 2 0 0	A TO SERVICE			ng zero
Close Out Construction Contracts CM CM Project Completion Declared CM Project Contract Completion Declared CM CM CM CM CM CM CM	CV6079	Project Construction Complete	CM				entités e	**************************************		0 00 0 0 00 0 0 00 0	14 14 1 14 14 1 10 14 1		100 PM 2					* ************************************	 a ca de a ca de a ca de			1 1	(9) (4) (9) (4) (4) (5) (4) (4) (4)			17 A 180
Construction Contracts Complete	CV6080	Close Out Construction Contracts	CM		1			-					1		#								i i i i	1		
Cooper Completion Declared CM CM CM CM CM CM CM C	CV6089	Construction Contracts Complete	CM	1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2			ce an e an eg n en saecos de basas s or we com				and the second s				1 (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1)		28 20 40 24 46 40 0 7 7	F 90 30	 			errana erran	B E I	1 20 20 1 1 20 27 9		
E: Bureau of Design & Construction Services Bureau of Design & Construction Services	CV6090	Close Out A/E Contract	CM			(m) () ()	POSITION OF THE PARTY OF THE PA		est technic	en Williams			TO S					# W	 C DE CO				0 0 0 000 0 0 000 0 0000			5 DPS /
r to section "IV Project Schedule" of the e of Work for contract phase durations. Bureau of Design & Construction Services	CV6092	Project Completion Declared	₹			**************************************					or and those particles of the control of the contro	-					**************************************			** ** ** ** ** ** ** ** **	19 mm m				101111 101110 1011 1011 1011 1011 1011	are s
r to section "IV Project Schedule" of the e of Work for contract phase durations.				,	•	*						4				ž									== == == =	
*******	NOTE Refe	: er to section "IV Project Schedule" of the ne of Work for contract nhace durations	DBCA - TE		reau	of L	 esign	38 11	Cons		fion (Serv	ices	Shee	130f3		6					r				
© Primavera Systems, Inc.		© Primavera Systems, Inc.														1	2						7			



Project Site Location Map

NJDOT Sayreville Maintenance Yard

EXHIBIT 'B'



Project Location
NJDOT Sayreville Maintenance Yard


EXHIBIT 'B'



Project Site


NJDOT Sayreville Maintenance Yard

EXHIBIT 'B'



Project Site Location Map
NJDOT Manahawkin Maintenance Yard

EXHIBIT 'B'



Project Location
NJDOT Manahawkin Maintenance Yard

EXHIBIT 'B'



Project Site

NJDOT Manahawkin Maintenance Yard **EXHIBIT 'B'**

NJDOT Sayreville Maintenance







NJDOT Manahawkin Maintenance




Yard



Photos


NJDOT Maintenance Yards

EXHIBIT 'C'



Drawings NJDOT Manahawkin Maintenance Yard

EXHIBIT 'D'



Drawings

NJDOT Sayreville Maintenance Yard

EXHIBIT 'D'