

**FY 2007-10 STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM
New Jersey Department of Transportation Projects**

<i>PROJECT NAME</i>	<i>Project ID No.</i>	<i>TIP No.</i>
Route 24, I-287 Interchange to West of Route 124 Interchange, Resurfacing	04382	04382

This project consists of milling and resurfacing Route 24 in both directions from the vicinity of milepost 0 to 6.8 in Morris and Essex Counties.

The roadway within the project limits is in generally poor condition, exhibiting rutting, high-severity wheel path fatigue cracking, high-severity potholes and severely deteriorated longitudinal joints between the right lane and shoulder. The outside shoulder is generally in poor condition. Extensive patching was performed in Spring 2004 by Region North Maintenance Contract in which portions of the travel lanes were milled 2 inches and resurfaced 2 inches. There are a few inlets within the project limits. Guiderail and bridge structures exist between the project limits. There are existing raised pavement markers within the project limits. Existing curb reveal varies from 4 to 6 inches.

This pavement preservation project is focused on extending pavement life and improving serviceability. Only resurfacing and incidentals required to facilitate the resurfacing as outlined in the scope of work for 3R projects will be done.

COUNTY: Morris Essex

MUNICIPALITY: Various

MILEPOSTS: 0 - 6.8

STRUCTURE NO.: N/A

LEGISLATIVE DISTRICT: 21 25 26 SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Highway Resurfacing

MPO	Phase	Fund	FY 2007	FY 2008	FY 2009	FY 2010	FY 2011
NJTPA	CON	STATE	\$12,600,000				