

New Jersey Department of Transportation

1035 Parkway Avenue, PO Box 600, Trenton, New Jersey 08625-0600

Baseline Document Change Announcement

ANNOUNCEMENT: BDC18S-17

DATE: January 31, 2019

SUBJECT: Miscellaneous changes
 - **Revision to the 2007 Standard Specifications for Road and Bridge Construction, Subsection 109.08, Subpart 507.03.02, and Subsection 703.03.**

Subsection 109.08, Subpart 507.03.02, and Subsection 703.03 of the *2007 Standard Specifications for Road and Bridge Construction* have been revised to provide clarifications.

The following revisions have been incorporated into the Standard Inputs (SI 2007).

109.08 AS-BUILT QUANTITIES

THE FOLLOWING IS ADDED:

If prior to the issuance of the Final Certificate, the Department determines there is an error in the provided as-built quantities, the Department will provide a revised list to the Contractor for review. Accept or reject the revised as-built quantities as described above.

507.03.02 Constructing Bridge Decks

N. Concrete Deck Surface Requirements

1. Acceptance Testing.

THE FOLLOWING IS ADDED TO TABLE 507.03.02-02

Table 507.03.02-2 Reduction Per Lot of Deck Slab Concrete Due to Nonconformance with Surface Requirements	
Lot Percent Defective Length	Reduction Per Lot, Percent
25.0 – 34.9 (Manually finished deck)	12.0

703.03 CONSTRUCTION

THE SECOND PARAGRAPH AS IT APPEARS IN THE SI IS CHANGED TO:

After placing the highway lighting system or temporary highway lighting system into operation, inspect the lighting system every 2 months. If the temporary lighting system fails or becomes damaged, inform the RE, repair and restore the system to normal operation. Ensure workers assigned to such repair work continuously until the lighting system is restored to normal operation.

If it is determined that the highway lighting system or temporary highway lighting system fails or becomes damaged in between inspections, repair and restore the system to normal operation. Begin repair of the signal system within 2 hours of receiving notice of damage or malfunction from the Department, State police, or local authorities. Ensure workers assigned to such repair work continuously until the lighting system is restored to normal operation.

Implementation Code R (ROUTINE)

Changes must be implemented in all applicable Department projects scheduled for Final Design Submission at least one month after the date of the BDC announcement. This will allow designers to make necessary plan, specifications, and estimate/proposal changes without requiring the need for an addenda or postponement of advertisement or receipt of bids.

Recommended By:



Paul F. Schneider
Director
Capital Program Support

Approved By:



Snehal Patel, P.E., PMP
Assistant Commissioner
Capital Program Management
and State Transportation Engineer