# **SCOPE OF WORK**

# **Fire Protection Upgrades**

New Lisbon Developmental Center New Lisbon, Burlington County, New Jersey

Project No. M1583-00

# STATE OF NEW JERSEY

Honorable Philip D. Murphy, Governor Honorable Sheila Y. Oliver, Lt. Governor

# **DEPARTMENT OF THE TREASURY**

Elizabeth Maher Muoio, Treasurer



## DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION

Christopher Chianese, Director

Date: July 21, 2023

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

# **TABLE OF CONTENTS**

SEC'	TION	PAGE
I.	OBJECTIVE	4
II.	CONSULTANT QUALIFICATIONS	4
A.	CONSULTANT & SUB-CONSULTANT PRE-QUALIFICATIONS	
III.	PROJECT BUDGET	4
A. B. C.	CONSTRUCTION COST ESTIMATE (CCE)	4
IV.	PROJECT SCHEDULE	5
A. B.	SCOPE OF WORK DESIGN & CONSTRUCTION SCHEDULE	
V.	PROJECT SITE LOCATION & TEAM MEMBERS	6
	PROJECT SITE ADDRESS PROJECT TEAM MEMBER DIRECTORY DPMC Representative:	7
VI.	PROJECT DEFINITION	7
A. B.	BACKGROUNDFUNCTIONAL DESCRIPTION OF THE BUILDINGS	
VII.	CONSULTANT DESIGN RESPONSIBILITIES	8
A. B. C. D.	NEW FIRE ALARM SYSTEM  CONTRACTOR USE OF THE PREMISES  HAZARDOUS BUILDING MATERIALS.  EXISTING DOCUMENTATION	12
VIII	I. PERMITS & APPROVALS	14
A. B.	NJ UNIFORM CONSTRUCTION CODE PLAN REVIEW AND PERMITOTHER REGULATORY AGENCY PERMITS, CERTIFICATES AND APPROVALS	
IX.	ENERGY INCENTIVE PROGRAM	17
X.	ALLOWANCES	18
A.	PLAN REVIEW AND PERMIT FEE ALLOWANCE	18

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

XIII.	EXHIBITS	21
XII.	CONTRACT DELIVERABLES	21
XI.	SOW SIGNATURE APPROVAL SHEET	20
D.	HAZARDOUS MATERIALS CONSTRUCTION ADMINISTRATION ALLOWANCE	19
C.	HAZARDOUS MATERIALS ABATEMENT DESIGN ALLOWANCE	19
B.	HAZARDOUS MATERIALS TESTING AND REPORT ALLOWANCE	18
4.	Consultant Fee:	18
3.	Applications:	18
	Permit Costs:	
1.	Permits:	18

- A. SAMPLE PROJECT SCHEDULE FORMAT
- B. PROJECT SITE LOCATION MAP
- C. BUILDING LIST
- D. CONTRACTOR RULES AND REGULATIONS

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

## I. OBJECTIVE

The objective of this project is to upgrade the fire protection systems at New Lisbon Developmental Center in Burlington County, New Jersey.

## II. CONSULTANT QUALIFICATIONS

## A. CONSULTANT & SUB-CONSULTANT PRE-QUALIFICATIONS

The Consultant shall be a firm pre-qualified with the Division of Property Management & Construction (DPMC) in the following discipline(s):

#### • P010 Fire Protection Engineering

The Consultant shall also have in-house capabilities or Sub-Consultants pre-qualified with DPMC in:

- P025 Estimating/ Cost Analysis
- P037 Asbestos Design
- P038 Asbestos Safety Control Monitoring
- P065 Lead Paint Evaluation

As well as, <u>any and all</u> other Architectural, Engineering and Specialty Disciplines necessary to complete the project as described in this Scope of Work (SOW).

## III. PROJECT BUDGET

## A. CONSTRUCTION COST ESTIMATE (CCE)

The initial Construction Cost Estimate (CCE) for this project is \$4,561,544.

The Consultant shall review this Scope of Work and provide a narrative evaluation and analysis of the accuracy of the proposed project CCE in its technical proposal based on its professional experience and opinion.

# B. CURRENT WORKING ESTIMATE (CWE)

The Current Working Estimate (CWE) for this project is \$6,560,000.

**PROJECT LOCATION: New Lisbon Developmental Center** 

PROJECT NO: M1583-00 DATE: July 21, 2023

The CWE includes the construction cost estimate and all consulting, permitting and administrative fees.

The CWE is the Client Agency's financial budget based on this project Scope of Work and shall not be exceeded during the design and construction phases of the project unless DPMC approves the change in Scope of Work through a Contract amendment.

#### C. CONSULTANT'S FEES

The construction cost estimate for this project *shall not* be used as a basis for the Consultant's design and construction administration fees. The Consultant's fees shall be based on the information contained in this Scope of Work document and the observations made and/or the additional information received during the pre-proposal meeting.

## IV. PROJECT SCHEDULE

Issue Plan Release

#### A. SCOPE OF WORK DESIGN & CONSTRUCTION SCHEDULE

The following schedule identifies the estimated design and construction phases for this project and the estimated durations.

#### PROJECT PHASE **ESTIMATED DURATION (Calendar Days)** 1. Site Access Approvals & Schedule Design Kick-off Meeting 14 2. Schematic Design Phase 42 14 Project Team & DPMC Plan/Code Unit Review & Comment 3. Design Development Phase 42 14 Project Team & DPMC Plan/Code Unit Review & Comment 4. Final Design Phase 42 14 Project Team & DPMC Plan/Code Unit Review & Approval 5. Final Design Re-Submission to Address Comments 7 Project Team & DPMC Plan/Code Unit Review & Approval 14 6. DCA Submission Plan Review **30** 7. Permit Application Phase 7

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

8.	Bid Phase	42
9.	Award Phase	28
10.	Construction Phase	180
11.	Project Close Out Phase	30

# B. CONSULTANT'S PROPOSED DESIGN & CONSTRUCTION SCHEDULE

The Consultant shall submit a project design and construction schedule with its technical proposal that is similar in format and detail to the schedule depicted in **Exhibit 'A'**. The schedule developed by the Consultant shall reflect its recommended project phases, phase activities, activity durations.

A written narrative shall also be included with the technical proposal explaining the schedule submitted and the reasons why and how it can be completed in the time frame proposed by the Consultant.

This schedule and narrative will be reviewed by the Consultant Selection Committee as part of the evaluation process and will be assigned a score commensurate with clarity and comprehensiveness of the submission.

# V. PROJECT SITE LOCATION & TEAM MEMBERS

#### A. PROJECT SITE ADDRESS

The location of the project site is:

New Lisbon Developmental Center 1 Bennion Ave/Route 72 (Just South of Route 70) New Lisbon, Burlington County, NJ

See Exhibit 'B' for the project site location map.

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

#### B. PROJECT TEAM MEMBER DIRECTORY

The following are the names, addresses, and phone numbers of the Project Team members.

## 1. **DPMC Representative:**

Name: Amit Mehta, Project Manager

Address: Division of Property Management & Construction

20 West State Street, 3<sup>rd</sup> Floor

Trenton, NJ 08608-1206

Phone No: (609) 292-1905

E-Mail: Amit.Mehta@treas.nj.gov

### 2. Department of Human Services:

Name: Christian Casteel, Director

Address: Department of Human Services

222 South Warren Street, PO Box 700

Trenton, New Jersey 08625

Phone No: (609) 984-5501

E-Mail: <u>christian.casteel@dhs.nj.gov</u>

#### VI. PROJECT DEFINITION

#### A. BACKGROUND

The New Lisbon Developmental Center is located in Burlington County and was founded in 1914 and the cottages of the facility were constructed in the late 1960's. It is the home for approximately 248 mentally and physically challenged individuals. The Center is manned 24-hours a day, 7 days a week. The Center provides a foundation for training, learning and maintaining health while enhancing the quality of life for individuals who reside on the grounds.

#### B. FUNCTIONAL DESCRIPTION OF THE BUILDINGS

The existing fire alarm system is a Johnson Controls/Simplex system in approximately 30 Building. There is a standalone Notifer panel in the Academic Building, and Notifer panels in the MSU complex, with MSA A and MSU B panels reporting to a remote annunciator in Ivy. All Notifier systems are not addressable but do report to the campus head end panel in Administration. DHS seeks to replace the entire campus system with a non-proprietary, open-

**PROJECT LOCATION: New Lisbon Developmental Center** 

PROJECT NO: M1583-00 DATE: July 21, 2023

protocol, addressable system and if possible would prefer to keep a similar head end arrangement, but would consider a system with multiple closed loops reporting to the Administration building.

The facility is seeking a fully addressable system and replacement of the remote dialer. See **Exhibit 'C'** for a list of buildings.

There is a fiber backbone in conduit that may be usable to tie in new equipment.

Most of the Asbestos Containing Materials have been abated. However, there may still be some ACM's, especially in mechanical spaces.

The fire suppression system will remain and connect to the new fire alarm system.

In 2012 under DPMC Project A1106-00, the facility added natural gas boilers to every building and no longer had use for heating previously supplied from the power house. Battery powered carbon monoxide detectors were added. The facility desires addressable CO detectors as part of the new system.

## VII. CONSULTANT DESIGN RESPONSIBILITIES

#### A. NEW FIRE ALARM SYSTEM

### 1. Survey/Needs Assessment:

Conduct a survey of the buildings to determine the existing conditions of all areas that will be impacted by the installation of the new fire alarm system and the site specific design requirements for this project.

The survey/needs assessment shall include, but not be limited to the following:

- Provide an analysis of which manufacturers can meet the non-proprietary, open protocol and addressability needs of the facility.
- Provide a review of the Centers for Medicare & Medicaid Services (CMS) citations related to fire suppression main post indicating valve (PIV) monitoring in accordance with NFPA 99 and 101, 2012 edition.
- Identify all existing fire detection system components, both operable and inoperable, that shall be removed and replaced as part of this project.
- Identify all fire suppression system and flow control valves that require monitoring by the new fire detection system.

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

• Identify building systems and components that require monitoring (duct work, air handlers, etc.) and any other conditions that need to be monitored by the fire detection system.

- Consult with facility staff and identify the appropriate location for all new remote annunciator panels. Determine the design requirements for space needs, existing equipment relocation, electrical power, tie-in to the main alarm panel, and provisions for a protected environment at each panel site location where required.
- Identify the location and space requirements for the main fire alarm panel.
- Identify the design requirements and exact routing of all new electrical distribution power wiring, if necessary, to the fire detection system and related components and the upgrades required for any existing electrical system component.
- Identify all obstructions that must be altered, relocated, or removed in order to install the new fire detection system.
- Identify the requirements for power to run the system and the availability of output devices to enable local as well as remote monitoring.
- Identify the design requirements for backup power, through batteries and/or UPS, so that a loss of power, for any reason will not limit the operation of the detection and annunciation of the system.
- Survey the existing suppression system and make design provisions to tie the suppression system into new panels as necessary.
- Consultant shall provide recommendations to connect the existing panels that are still supported by the manufacturers to the new main panel.

The survey/needs assessment shall be submitted in a hardcopy report (four copies) and digital copy as part of the Schematic Phase of the project and shall include an estimate of the construction cost based on the findings of the survey/needs assessment.

# 2. New System Design Criteria:

Provide the design and specifications to replace all of the existing fire alarm detectors, peripheral devices and panels at the facility with a new non-proprietary system. In addition, address the following as may be applicable.

- System shall be a non-proprietary, open protocol and fully addressable network system.
- Protection of the fire alarm system from electrical surges, spikes, sags, over-voltages, brownouts, and electrical noise.
- Addressability of devices and notifications made to the building fire alarm control panels and the facility main fire alarm station panel.
- All programmable devices must be able to have their addresses set without special equipment, tools, or programs. Changing of vandalized heads or devices must be able to be completed by facility maintenance staff without the requirement of special software or tools.
- Software requirements and compatibility with new devices.

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

• New smoke detectors shall be appropriate for the institution and approved by facility staff. Install heat detectors rather than smoke detectors in high humidity locations.

- As applicable, duct detectors shall be installed so they are accessible for repair or replacement. They shall be located in areas ensuring laminar flow across the detector. Do not locate them downstream of humidity injection points. Each duct detector shall have a LED that can be easily observed and located by the fire company and other interested parties. Each duct sensor shall be self-compensating for the effects of air velocity, temperature, humidity, and atmospheric pressure and not require field adjustments to compensate for the above effects.
- The building fire alarm control panels shall be wired to all peripheral alarm and initiating devices and tied into remote annunciator panels located in a convenient area near the fire department entrance to the buildings and shall be readily accessible and readily visible to fire fighters. The building fire alarm control panels and annunciator panels shall be tied into the existing or a new electrical power source at their location in the building.
- Consult with facility staff and provide additional annunciator panels in locations as needed.
- Provide a riser diagram drawing for the building fire alarm control panels that identifies their connections to the various circuits and peripheral initiating devices.
- Any new low voltage wiring, if necessary, from the fire alarm panels to the peripheral devices shall be concealed and run in wire mold or conduit, whichever is more appropriate for the building conditions, security requirements, efficiency, and cost effectiveness. Any exposed wiring installed above the ceiling shall be plenum fire rated cable in accordance with NEC Article 760 or must be protected in conduit. Protect exposed fire alarm wiring from potential rodent damage.
- The fire detection systems shall have emergency battery backup that is sized in accordance with all applicable codes. The battery supply shall be calculated to operate loads in a supervisory mode for twenty-four (24) hours for central station systems and remote supervisory systems. Batteries shall be sized at 125% of the calculated size to compensate for deterioration and aging during the battery life cycle. Battery calculations shall be submitted to the DPMC Code & Design Review Unit for record.
- Provide a battery charging circuit for each standby battery bank in the system. The
  charger shall be automatic in design, adjusting the charge rate to the condition of the
  batteries. All system battery charge rates and terminal voltages shall be read using the
  fire alarm control panel LCD display in the service mode indicating directly in volts and
  amps.
- Address redundancy within the system such that a failure of the alarm system within one building does not impact other buildings.
- The building fire alarm panel, annunciators, and each power supply, addressable circuit, audible circuit, visual circuit, amplifier, etc. shall be designed to have 25% spare capacity. System operating hardware shall be functionally expandable by installing additional solid state plug-in modules. Note that the installation of additional plug-in modules shall not require the replacement of existing equipment, components, or accessories.

**PROJECT LOCATION:** New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

• The consultant shall specify smoke and heat detectors, pull stations, remote annunciators, and appurtenances, to the extent possible, as ligature resistant hardware. Fire alarm control panels that may be in areas where patients have access should also meet this requirement. Any conduit runs shall be designed in a manner to reduce ligature risk. In the event that equipment is not available in ligature resistant types, the design consultant shall provide specifications and/or design details to address the ligature risk associated with the hardware. The design consultant will be provided with the current design guide used as a benchmark for meeting this requirement upon commencement of the design phase.

#### 3. System Tests:

A written "Acceptance Test Procedure" (ATP) for testing the new fire detection system and components, as applicable, shall be prepared by the Consultant in accordance with all applicable codes and standards and included in the specification.

Upon completion of the system installation, the system manufacturer shall be responsible for the performance of the ATP, demonstrating the function of the system and verifying the correct operation of all system components, circuits and programming.

The system test shall be witnessed and approved by the Department of Community Affairs (DCA). The Consultant shall provide ample notification time when arranging the demonstration with DCA, DPMC Project Team members, Client Agency, Contractor, and the equipment manufacturer.

Upon final acceptance of the system, the Contractor shall provide a complete as-built color-coded wiring diagram. The diagram shall include a written statement signed by the Contractor and manufacturer's representative that the diagram has been corrected to include field changes and does represent the system installed.

The fire detection manufacturer shall provide system training to the facility personnel as described in Section VIII, paragraph M of this document.

#### 4. Spare Parts:

A spare parts list shall be prepared and items purchased as part of this project for all critical items necessary for the successful operation of the fire detection system such as detectors, fire alarm fuses, switches, relays, LED lights, etc. Instructions shall be included for the operation and care of the system. Written instructions shall also be included with the final equipment and maintenance brochure.

**PROJECT LOCATION: New Lisbon Developmental Center** 

PROJECT NO: M1583-00 DATE: July 21, 2023

#### B. CONTRACTOR USE OF THE PREMISES

Refer to **Exhibit 'D'** and work with the Project Team to add any additional special security and policy requirements that must be followed during all work conducted at the facility and include this information in Division 1 of the specification.

Develop procedures for personnel to access the project site and construction areas, and provide the names and phone numbers of approved escorts when needed.

#### C. HAZARDOUS BUILDING MATERIALS

The Consultant shall survey the buildings and, if deemed necessary, collect samples of materials that will be impacted by the construction/demolition activities and analyze them for the presence of hazardous materials including:

- 1. Asbestos in accordance with N.J.A.C. 5:23-8, Asbestos Hazard Abatement Subcode.
- 2. Lead in accordance with N.J.A.C. 5:17, Lead Hazard Evaluation and Abatement Code.
- 3. PCB's in accordance with 40 CFR 761, Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions. Consultant shall engage a firm certified in the testing and analysis of materials containing PCB's.

Consultant shall document their procedure, process and findings and prepare a "Hazardous Materials Survey Report" identifying building components impacted by construction activities requiring hazardous materials abatement. Consultant shall provide three copies of the "Hazardous Materials Survey Report" to the Project Manager.

Consultant shall estimate the cost of hazardous materials sample collection, destructive testing as necessary, tests and analysis and preparation of the Hazardous Materials Survey Report and include that amount in their fee proposal line item entitled "Hazardous Materials Testing and Report Allowance", refer to paragraph XI.B.

Based on the Hazardous Materials Survey Report, Consultant shall provide construction documents for abatement of the hazardous materials impacted by the work in accordance with the applicable code, subcode and Federal regulations.

Consultant shall estimate the cost to prepare construction documents for hazardous materials abatement and include that amount in their fee proposal line item entitled "Hazardous Materials Abatement Design Allowance", refer to paragraph XI.C.

Consultant shall estimate the cost to provide "Construction Monitoring and Administration Services" for hazardous materials abatement activities and include that amount in their fee

**PROJECT LOCATION:** New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

proposal line item entitled "Hazardous Materials Construction Administration Allowance", refer to paragraph XI.D.

There shall be no "mark-up" of subconsultant or subcontractor fees if subconsultants or subcontractors are engaged to perform any of the work defined in paragraph VII.C "Hazardous Building Materials". All costs associated with managing, coordinating, observing and administrating subconsultants and subcontractors performing hazardous materials sampling, testing, analysis, report preparation, hazardous materials construction administration services shall be included in the consultant's lump sum fee proposal.

#### D. EXISTING DOCUMENTATION

Copies of the following documents will be provided to each Consulting firm at the pre-proposal meeting to assist in the bidding process.

- DPMC Project M1535-03: Controlled Egress Doors, Fern Cottage, 10/3/2019, Lammey & Giorgio
- DPMC Project M1538-00: **Police Relocation**, 11/30/2021, Ronald A. Sebring Associates, LLC
- DBC Project M1253-00: **Moderate Security Unit Building Addition and Alterations**, May, 1997, The Lichtman Associates, P.C.
- DPMC Project A1106-00: **Gas Fired Heating Boilers**, 4/13/2012, Miller-Remick, Corporation
- Asbestos Containing Materials Survey Reports, Various Buildings, 1996, GA Environmental Services
- DPMC Project M1541-00: **Oak and Red Oak Fire Suppression Upgrades**, 5/3/2022, Gannett Fleming Architects, Inc.
- DPMC Project M1367-00: **NLDC Telecom Upgrade**, 18 December, 2009, CH2MHill Lockwood Greene
- DPMC Project M1258-00: Fire/Life Safety Systems New Lisbon Developmental Centers, 11/21/1997, STV Incorporated
- DPMC Project M1542-00: New Secondary Egress Various Buildings, 4/22/2022, Ronald A. Sebring Associates, LLC

Review these documents and any additional information that may be provided at a later date such as reports, studies, surveys, equipment manuals, as-built drawings, etc. The State does not attest to the accuracy of the information provided and accepts no responsibility for the consequences of errors by the use of any information and material contained in the documentation provided. It shall be the responsibility of the Consultant to verify the contents and assume full responsibility for any determination or conclusion drawn from the material used. If the information provided is insufficient, the Consultant shall take the appropriate actions necessary to obtain the additional information required.

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

All original documentation shall be returned to the provider at the completion of the project.

## VIII. PERMITS & APPROVALS

#### A. NJ UNIFORM CONSTRUCTION CODE PLAN REVIEW AND PERMIT

The project construction documents must comply with the latest adopted edition of the NJ Uniform Construction Code (NJUCC).

The latest NJUCC Adopted Codes and Standards can be found at:

http://www.state.nj.us/dca/divisions/codes/codreg/

#### 1. NJ Uniform Construction Code (NJUCC) Plan Review

Consultant shall estimate the cost of the NJUCC Plan Review by DCA and include that amount in their fee proposal line item entitled "Plan Review and Permit Fee Allowance", refer to paragraph XI.A.

Upon approval of the Final Design Phase Submission by DPMC, the Consultant shall submit the construction documents to the Department of Community Affairs (DCA), Bureau of Construction Project Review to secure a complete plan release.

As of July 25, 2022, the Department of Community Affairs (DCA) is only accepting digital signatures and seals issued from a third party certificate authority. The DCA ePlans site can be found at:

https://www.nj.gov/dca/divisions/codes/offices/ePlans.html

Procedures for submission to the DCA Plan Review Unit can be found at:

https://www.state.nj.us/dca/divisions/codes/forms/pdf bcpr/pr app guide.pdf

Consultant shall complete the "Project Review Application" and include the following on Block 5 as the "Owner's Designated Agent Name":

Joyce Spitale, DPMC PO Box 235 Trenton, NJ 08625-0235 Joyce.Spitale@treas.nj.gov 609-943-5193

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

The Consultant shall complete the NJUCC "Plan Review Fee Schedule", determine the fee due and pay the NJUCC Plan Review fees, refer to Paragraph X.A. The NJUCC "Plan Review Fee Schedule" can be found at:

http://www.state.nj.us/dca/divisions/codes/forms/pdf bcpr/pr fees.pdf

#### 2. NJ Uniform Construction Code Permit

Upon receipt of a complete plan release from the DCA Bureau of Construction Project Review, the Consultant shall complete the NJUCC permit application and all applicable technical subcode sections. The "Agent Section" of the application and certification section of the building sub-code section shall be signed. These documents, with six (6) sets of DCA approved, signed and sealed construction documents shall be forwarded to the DPMC Project Manager.

The Consultant may obtain copies of all NJUCC permit applications at the following website:

http://www.state.nj.us/dca/divisions/codes/forms/

All other required project permits shall be obtained and paid for by the Consultant in accordance with the procedures described in Paragraph VIII.B.

#### 3. Prior Approval Certification Letters:

The issuance of a construction permit for this project may be contingent upon acquiring various "prior approvals" as defined by N.J.A.C. 5:23-1.4. It is the Consultant's responsibility to determine which prior approvals, if any, are required. The Consultant shall submit a general certification letter to the DPMC Plan & Code Review Unit Manager during the Permit Phase of this project that certifies all required prior approvals have been obtained.

In addition to the general certification letter discussed above, the following specific prior approval certification letters, where applicable, shall be submitted by the Consultant to the DPMC Plan & Code Review Unit Manager: Soil Erosion & Sediment Control, Water & Sewer Treatment Works Approval, Coastal Areas Facilities Review, Compliance of Underground Storage Tank Systems with N.J.A.C. 7:14B, Pinelands Commission, Highlands Council, Well Construction and Maintenance; Sealing of Abandoned Wells with N.J.A.C. 7:9D, Certification that all utilities have been disconnected from structures to be demolished, Board of Health Approval for Potable Water Wells, Health Department Approval for Septic Systems. It shall be noted that in accordance with N.J.A.C. 5:23-2.15(a)5, a permit cannot be issued until the letter(s) of certification is received.

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

### 4. Multi-building or Multi-site Permits:

A project that involves many buildings and/or sites requires that a separate permit shall be issued for each building or site. The Consultant must determine the construction cost estimate for *each* building and/or site location and submit that amount where indicated on the permit application.

## 5. Special Inspections:

In accordance with the requirements of the New Jersey Uniform Construction Code N.J.A.C. 5:23-2.20(b), Bulletin 03-5 and Chapter 17 of the International Building Code, the Consultant shall be responsible for the coordination of all special inspections during the construction phase of the project.

Bulletin 03-5 can be found at:

http://www.state.nj.us/dca/divisions/codes/publications/pdf bulletins/b 03 5.pdf

#### a. Definition:

Special inspections are defined as an independent verification by a certified Special Inspector for Class I buildings and smoke control systems in any class building. The special inspector is to be independent from the Contractor and responsible to the Consultant so that there is no possible conflict of interest.

Special inspectors shall be certified in accordance with the requirements in the New Jersey Uniform Construction Code.

#### b. Responsibilities:

The Consultant shall submit with the permit application, a list of special inspections and the agencies or special inspectors that will be responsible to carry out the inspections required for the project. The list shall be a separate document, on letter head, signed and sealed.

# B. OTHER REGULATORY AGENCY PERMITS, CERTIFICATES AND APPROVALS

The Consultant shall identify and obtain all other State Regulatory Agency permits, certificates, and approvals that will govern and affect the work described in this Scope of Work. An itemized list of these permits, certificates, and approvals shall be included with the Consultant's Technical Proposal and the total amount of the application fees should be entered in the Fee Proposal line item entitled, "Permit Fee Allowance."

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

The Consultant may refer to the Division of Property Management and Construction "Procedures for Architects and Engineers Manual", Paragraph "9. REGULATORY AGENCY APPROVALS" which presents a compendium of State permits, certificates, and approvals that may be required for this project.

The Consultant shall determine the appropriate phase of the project to submit the permit application(s) in order to meet the approved project milestone dates.

Where reference to an established industry standard is made, it shall be understood to mean the most recent edition of the standard unless otherwise noted. If an industry standard is found to be revoked, or should the standard have undergone substantial change or revision from the time that the Scope of Work was developed, the Consultant shall comply with the most recent edition of the standard.

## IX. ENERGY INCENTIVE PROGRAM

The Consultant shall review the programs available on the "New Jersey's Clean Energy Program" website at: <a href="http://www.njcleanenergy.com">http://www.njcleanenergy.com</a> as well as New Jersey electric and gas utility websites to determine if any proposed upgrades to the mechanical and/or electrical equipment and systems for this project qualify for "New Jersey Clean Energy Program" or utility approved rebates and incentives.

Consultant shall identify all rebates and incentives in their technical proposal.

The Consultant shall be responsible to complete the appropriate registration forms and applications, provide any applicable worksheets, manufacturer's specification sheets, calculations, attend meetings, and participate in all activities with designated representatives of the programs and utility companies to obtain the entitled financial incentives and rebates for this project.

All costs associated with this work shall be estimated by the Consultant and the amount included in the base bid of its fee proposal.

**PROJECT LOCATION:** New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

## X. ALLOWANCES

#### A. PLAN REVIEW AND PERMIT FEE ALLOWANCE

The Consultant shall obtain and pay for all of the project permits in accordance with the guidelines identified below.

#### 1. Permits:

The Consultant shall determine the various permits, certificates, and approvals required to complete this project.

#### 2. Permit Costs:

The Consultant shall estimate the application fee costs for all of the required project permits, certificates, and approvals (excluding the NJ Uniform Construction Code permit) and include that amount in its fee proposal line item entitled "Plan Review and Permit Fee Allowance", refer to Paragraph IX.A. A breakdown of each permit and application fee shall be attached to the fee proposal for reference.

**NOTE:** The NJ Uniform Construction Code permit is excluded since it will be paid for by the State.

#### 3. Applications:

The Consultant shall complete and submit all permit applications to the appropriate permitting authorities and the costs shall be paid from the Consultant's permit fee allowance. A copy of the application(s) and the original permit(s) obtained by the Consultant shall be given to the DPMC Project Manager for distribution during construction.

#### 4. Consultant Fee:

The Consultant shall determine what is required to complete and submit the permit applications, obtain supporting documentation, attend meetings, etc., and include the total cost in the base bid of its fee proposal under the "Permit Phase" column.

Any funds remaining in the permit allowance will be returned to the State at the close of the project.

#### B. HAZARDOUS MATERIALS TESTING AND REPORT ALLOWANCE

Consultant shall estimate the costs to complete the hazardous materials survey, sample collection, testing and analysis and preparation of a "Hazardous Materials Survey Report" noted

PROJECT LOCATION: New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

in paragraph VII.C and enter that amount on their fee proposal line item entitled "Hazardous Materials Testing and Report Allowance". Consultant shall attach a detailed cost breakdown sheet for use by DPMC during the proposal review and potential fee negotiations. The cost breakdown sheet shall include, but not be limited to, the following information:

- Description of tasks and estimated cost for the following:
  - Sample collection
  - o Sample testing
  - o Preparation of an Hazardous Materials Survey Report

Any funds remaining in the Hazardous Materials Testing and Report Allowance will be returned to the State at the close of the project.

#### C. HAZARDOUS MATERIALS ABATEMENT DESIGN ALLOWANCE

Consultant shall estimate the costs to prepare construction documents for hazardous materials abatement noted in paragraph VII.C and enter that amount on their fee proposal line item entitled "Hazardous Materials Abatement Design Allowance". Consultant shall attach a detailed cost breakdown sheet for use by DPMC during the proposal review and potential fee negotiations. The cost breakdown sheet shall include a description of the tasks to be performed and the estimated cost of each task.

Any funds remaining in the Hazardous Materials Abatement Design Allowance will be returned to the State at the close of the project.

# D. HAZARDOUS MATERIALS CONSTRUCTION ADMINISTRATION ALLOWANCE

Consultant shall estimate the cost to provide Construction Monitoring and Administration Services for hazardous materials abatement as noted in paragraph VII.C and enter that amount on their fee proposal line item entitled "Hazardous Materials Construction Administration Allowance". Consultant shall attach a detailed cost breakdown sheet for use by DPMC during the proposal review and potential fee negotiations. The cost breakdown sheet shall include a description of the tasks to be performed and the estimated cost of each task.

Any funds remaining in the Hazardous Materials Construction Administration Allowance will be returned to the State at the close of the project.

**SOW APPROVED BY:** 

PROJECT LOCATION: New Lisbon Developmental Center

**PROJECT NO: M1583-00 DATE: July 21, 2023** 

#### XI. SOW SIGNATURE APPROVAL SHEET

This Scope of Work shall not be considered a valid document unless all signatures appear in each designated area below.

The Client Agency approval signature on this page indicates that they have reviewed the design criteria and construction schedule described in this project Scope of Work (including the subsequent contract deliverables and exhibits) and verifies that the work will not conflict with the existing or future construction activities of other projects at the site.

**SOW APPROVED BY:** ( 7/21/2023 WRIGHT, MANAGER DPMC PROJECT PLANNING & INITIATION 7/23/2023 **SOW APPROVED BY:**  $^{\prime\prime}$ CHRISTIAN CASTEEL, DIRECTOR **DATE** DEPARTMENT OF HUMAN SERVICES amit mehta 08/02/23 **SOW APPROVED BY:** AMIT MEHTA, PROJECT MANAGER **DATE** DPMC PROJECT MANAGEMENT GROUP 8/29/23

> RICHARD FLODMAND, DEPUTY DIRECTOR **DIV PROPERTY MGT & CONSTRUCTION**

DATE

**PROJECT LOCATION:** New Lisbon Developmental Center

PROJECT NO: M1583-00 DATE: July 21, 2023

### XII. CONTRACT DELIVERABLES

The following are checklists listing the Contract Deliverables that are required at the completion of each phase of this project. The Consultant shall refer to the DPMC publication entitled "Procedures for Architects and Engineers," 3.0 Edition, dated September 2022 available at <a href="https://www.nj.gov/treasury/dpmc/Assets/Files/ProceduresforArchitectsandEngineers.pdf">https://www.nj.gov/treasury/dpmc/Assets/Files/ProceduresforArchitectsandEngineers.pdf</a> for a detailed description of the deliverables required for each submission item listed. References to the applicable paragraphs of the "Procedures for Architects and Engineers" are provided.

Note that the Deliverables Checklist may include submission items that are "S.O.W. Specific Requirements". These requirements will be defined in the project specific scope of work and included on the deliverables checklist.

This project includes the following phases with the deliverables noted as "Required by S.O.W" on the Deliverables Checklist:

- SCHEMATIC DESIGN PHASE
- DESIGN DEVELOPMENT PHASE
- FINAL DESIGN PHASE
- PERMIT APPLICATION PHASE
- BIDDING AND CONTRACT AWARD
- CONSTRUCTION PHASE
- PROJECT CLOSE-OUT PHASE

#### XIII. EXHIBITS

- A. SAMPLE PROJECT SCHEDULE FORMAT
- B. PROJECT SITE LOCATION MAP
- C. BUILDING LIST
- D. CONTRACTOR RULES AND REGULATIONS

#### END OF SCOPE OF WORK

# Deliverables Checklist Schematic Design Phase

A/E Name:
-----------

A/E Manual		Required by S.O.W.		Previously Submitted		Enclosed	
Reference	Submission Item	Yes	No	Yes	No	Yes	No
13.4.1.	A/E Statement of Site Visit						
13.4.2.	Narrative Description of Project						
13.4.3.	Building Code Information Questionnaire						
13.4.4.	Space Analysis						
13.4.5.	Special Features						
13.4.6.	Catalog Cuts						
13.4.7.	Site Evaluation						
13.4.8.	Subsurface Investigation						
13.4.9.	Surveys						
13.4.10.	Arts Inclusion						
13.4.11.	Design Rendering						
13.4.12.	Regulatory Approvals						
13.4.13.	Utility Availability						
13.4.14.	Drawings (6 Sets)						
13.4.15.	Outline Specifications (6 Sets)						
13.4.16.	Current Working Estimate/Cost Analysis						
13.4.17.	Project Schedule						
13.4.18.	Formal Presentation						
13.4.19.	Scope of Work Compliance Statement						
13.4.20.	Schematic Design Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						
VII.A.1	Survey/Needs Assessment (4 copies + digital)						

This checklist shall be completed by the Design Consultant and included as the cover sheet of this submission document to the DPMC the status of all the deliverables required by the project specific Scope of Work.				
	, ,			sion t
Consultant Signature Date	Consultant Signature	 	 	

# Deliverables Checklist Design Development Phase

A/E Name:
-----------

A/E Manual	Required by S.O.W.		-	Previously Submitted		Enclosed	
Reference	Submission Item	Yes	No	Yes	No	Yes	No
14.4.1.	A/E Statement of Site Visit						
14.4.2.	Narrative Description of Project						
14.4.3.	Building Code Information Questionnaire						
14.4.4.	Space Analysis						
14.4.5.	Special Features						
14.4.6.	Catalog Cuts						
14.4.7.	Site Evaluation						
14.4.8.	Subsurface Investigation						
14.4.9.	Surveys						
14.4.10.	Arts Inclusion						
14.4.11.	Design Rendering						
14.4.12.	Regulatory Approvals						
14.4.13.	Utility Availability						
14.4.14.	Drawings (6 Sets)						
14.4.15.	Outline Specifications (6 Sets)						
14.4.16.	Current Working Estimate/Cost Analysis						
14.4.17.	Project Schedule						
14.4.18.	Formal Presentation						
14.4.19.	Plan Review/Scope of Work Compliance Statement						
14.4.20.	Design development Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						
					1		
					1		

This checklist shall be completed by the Design Consultant and included as the cover sheet of this submi					
document to the DPMC the status of all the deliverables requ	uired by the project specific Scope of Work.				
Consultant Signatura	 				
Consultant Signature	Date				

# Deliverables Checklist Final Design Phase

A/E Name:
-----------

A/E Manual		Required by S.O.W.		Previously Submitted		Enclosed	
Reference	Submission Item	Yes	No	Yes	No	Yes	No
15.4.1.	A/E Statement of Site Visit						
15.4.2.	Narrative Description of Project						
15.4.3.	Building Code Information Questionnaire						
15.4.4.	Space Analysis						
15.4.5.	Special Features						
15.4.6.	Catalog Cuts						
15.4.7.	Site Evaluation						
15.4.8.	Subsurface Investigation						
15.4.9.	Surveys						
15.4.10.	Arts Inclusion						
15.4.11.	Design Rendering						
15.4.12.	Regulatory Approvals						
15.4.13.	Utility Availability						
15.4.14.	Drawings (6 Sets)						
15.4.15.	Outline Specifications (6 Sets)						
15.4.16.	Current Working Estimate/Cost Analysis						
15.4.17.	Project Schedule						
15.4.18.	Formal Presentation						
15.4.19.	Plan Review/Scope of Work Compliance						
	Statement						
15.4.20.	Final Design Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements				1		

This checklist shall be completed by the Design Consultant an document to the DPMC the status of all the deliverables requ	
Consultant Signature	 Date

# **Deliverables Checklist Permit Application Phase**

16.4. Drav 16.5. Spe 16.6. Curi 16.7. Proj 16.8. Plar Stat	Submission Item  UCC Permit Application wings, Signed and Sealed (6 Sets) cifications, Signed and Sealed (6 Sets) rent Working Estimate/Cost Analysis ject Schedule	Yes	No	Yes	No	Yes	No
16.4. Drav 16.5. Spec 16.6. Curr 16.7. Proj 16.8. Plar Stat	wings, Signed and Sealed (6 Sets) cifications, Signed and Sealed (6 Sets) rent Working Estimate/Cost Analysis						
16.5. Special	cifications, Signed and Sealed (6 Sets) rent Working Estimate/Cost Analysis						
16.6. Curi 16.7. Proj 16.8. Plar Stat	rent Working Estimate/Cost Analysis						
16.7. Proj 16.8. Plar Stat							
16.8. Plar Stat	ject Schedule						
Stat							
16.9. Peri	n Review/Scope of Work Compliance tement						
	mit Application Phase Deliverables ecklist						
S.O.W. Reference	.W. Specific Requirements						
							ļ
							-
							-
							-

Date

**Consultant Signature** 

# Deliverables Checklist Bidding and Contract Award Phase

A/E Name:

A/E Manual		Requir S.O	-	Previ Subm	-	Encl	osed
Reference	Submission Item	Yes	No	Yes	No	Yes	No
17.1.1.	Notice of Advertising						
17.1.2.	Bid Proposal Form						
17.1.3.	Bid Clearance Form						
17.1.4.	Drawings (6 Sets)						
17.1.5.	Specifications (6 Sets)						
17.1.6.	Construction Schedule						
17.3	Pre-Bid Conference/Mandatory Site Visit						
17.3.1.	Meeting Minutes						
17.4	Bulletins						
17.5	Post Bid Meeting						
17.6.	Contract Award "Letter of Recommendation"						
17.8.	Bid Protests - Hearings						
17.9.	Bidding and Contract Award Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						
	shall be completed by the Design Consultant and he DPMC the status of all the deliverables require						sion to
	Consultant Signature			Date			

# **Deliverables Checklist Construction Phase**

A/E Name: _			

A/E Manual		Requi S.O	red by .W.	Previ Subm	ously nitted	Encl	osed
Reference	Submission Item	Yes	No	Yes	No	Yes	No
18.2.	Pre-Construction Meeting						
18.3.	Submittal Log						
18.4.	Construction Schedule						
18.5.	Project Progress Meetings						
18.7.	Contractor's Invoicing and Payment Process						
18.8.	Contractor Submittals						
18.10.	Testing						
18.11.	Shop Drawings (6 Sets)						
18.12.	As-Built & Record Set Drawings (6 Sets)						
18.13.	Change Orders						
18.14.	Construction Photographs						
18.15.	Field Observations						
18.17.	Construction Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						

This checklist shall be completed by the Design Consultant document to the DPMC the status of all the deliverables re	
Consultant Signature	Date

# Deliverables Checklist Project Close-Out Phase

A/E Manual		Requii S.O			ously nitted	Encl	osed
Reference	Submission Item	Yes	No	Yes	No	Yes	No
19.3.	Development of Punch List and Inspection Reports						
19.5.	Determination of Substantial Completion						
19.6.	Correction/Completion of Punch List						
19.7.	Submission of Close-Out Documentation						
19.7.1.	As-Built and Record Sets of Drawing (6 Sets)						
19.8.	Final Payment						
19.9.1.	Contractors Final Payment						
19.9.2.	A/E's Final Payment						
19.10.	Project Close-Out Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements					l	I.

This checklist shall be completed by the Design Consultant and document to the DPMC the status of all the deliverables requir	
Consultant Signature	

February 7, 1997 **Rev.**: January 29, 2002

#### Responsible Group Code Table

The codes below are used in the schedule field "GRP" that identifies the group responsible for the activity. The table consists of groups in the Division of Property Management & Construction (DPMC), as well as groups outside of the DPMC that have responsibility for specific activities on a project that could delay the project if not completed in the time specified. For reporting purposes, the groups within the DPMC have been defined to the supervisory level of management (i.e., third level of management, the level below the Associate Director) to identify the "functional group" responsible for the activity.


CODE	DESCRIPTION	REPORTS TO ASSOCIATE DIRECTOR OF:
CM	Contract Management Group	Contract Management
CA	Client Agency	N/A
CSP	Consultant Selection and Prequalification Group	Technical Services
A/E	Architect/Engineer	N/A
PR	Plan Review Group	Technical Services
CP	Construction Procurement	Planning & Administration
CON	Construction Contractor	N/A
FM	Financial Management Group	Planning & Administration
OEU	Office of Energy and Utility Management	N/A
PD	Project Development Group	Planning & Administration

# **EXHIBIT 'A'**

	Description	Rspn Weeks	
<pr< td=""><td><proj></proj></td><td></td><td></td></pr<>	<proj></proj>		
Design	u		
CV3001	Schedule/Conduct Predesign/Project Kick-Off Mtg.		
CV3020	Prepare Program Phase Submittal	# W	
CV3021	Distribute Program Submittal for Review		
CV3027	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3022	Review & Approve Program Submittal	5	
CV3023	Review & Approve Program Submittal		
CV3024	Review & Approve Program Submittal		
CV3025	Consolidate & Return Program Submittal Comments		
CV3030	Prepare Schematic Phase Submittal	## W	
CV3031	Distribute Schematic Submittal for Review		
CV3037	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3032	Review & Approve Schematic Submittal		
CV3033	Review & Approve Schematic Submittal		
CV3034	Review & Approve Schematic Submittal	8	
CV3035	Consolidate & Return Schematic Submittal Comment		
CV3040	Prepare Design Development Phase Submittal	¥	
CV3041	Distribute D. D. Submittal for Review		
CV3047	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3042	Review & Approve Design Development Submittal		
CV3043	Review & Approve Design Development Submittal		
CV3044	Review & Approve Design Development Submittal		
CV3045	Consolidate & Return D.D. Submittal Comments		
CV3050	Prepare Final Design Phase Submittal	<b>YB</b>	
CV3051	Distribute Final Design Submittal for Review		
CV3052	Review & Approve Final Design Submittal	8	
CV3053	Review & Approve Final Design Submittal	æ	
CV3054	Review Final Design Submitl for Constructability	830	
NOTE:		DBCA - TEST Sheet 1 of 3	
Ref. Sco	Refer to section "IV Project Schedule" of the Scope of Work for contract phase durations.	Bureau of Design & Construction Services	IT 'A'
			T7 T7

The Content of the	Activity	<b>\</b>															ſ
A contract of the Design Submitted	A		Rspn						Weeks								
Submit Permit Application Documents   CM	CV3055	Review & Approve Final Design Submittal	₹												THE PERSON NAMED IN		THE REAL PROPERTY.
Subtrait Permit Application Documents   AB   Subtrait Permit Application Documents & Subtrait Permit Acquisition   CM   Subtrait Bidding Cost Analysis (DPMC-38)   CM   Subtrait Bidding Cost Cost Cost Cost Cost Cost Cost Cost	CV3056	Consolidate & Return Final Design Comments	₹		N 10 10								0 00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		500 5 50 5 50 5 50		
Contact   Cont	CV3060	Prepare & Submit Permit Application Documents	ΑE		the second										2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	v v	
Construction Contracts   Construction Contra	CV3068	Prepare & Submit Bidding Cost Analysis (DPMC-38)	CM														1 20
Avarage   Construction Contracts   CA	Plan R	Review-Permit Acquisition											100				
A ward	CV4001	Review Constr. Documents & Secure UCC Permit	R.				20 Mg	Color	Email							· · · · ·	en o i
Id Clearance	CV4010	Provide Funding for Construction Contracts	CA		25 Mo 100 26 400 Mo 27 27 Mo 27 27 Mo 27 27 Mo 27 27 Mo 27 27 Mo 27 Mo 2		10 10 10 10 10 10 10 10 10 10 10		* 00 0							2	- 100 FB
Start   Contracts   CP   Start	CV4020	Secure Bid Clearance	Æ					7 to 100 to 1									
Bids & Prep. Recommendation for Award CP Bids & Prep. Recommendation CP Bids & Prep. Recom	Advert	ise-Bid-Award															
Bids & Prep. Recommendation for Award CM Bids & Prep. Recommendation for Award CM Bids & Prep. Recommendation for Award CM onstruction Contracts/Issue NTP CM Start/Contract Work (25%) Complete COM Sconstruction Submittals COM Each Procurement Item Ordered COM Sconstruction Submittals COM Sconstruction Sub	CV5001	Advertise Project & Bid Construction Contracts	B								2 0				A SECURE	· · ·	
Bids & Prep. Recommendation for Award   AE	CV5010	Open Construction Bids	ප													5	COCCES TO ACT AND AND MACHINE AND ACT AND AND AND
Bids & Prep. Recommendation for Award         AE           onstruction Contracts/Issue NTP         CP           onstruction Star/Ussue NTP         CM           Star/Contract Work (25%) Complete         CON           construction Submittals         CON           construction Submittals         CON           c Submit Shop Drawings         CON           Work (50%+) Complete         CON           Performed Propertizet Schedule" of the         Bureau of Design & Construction Services	CV5011	Evaluate Bids & Prep. Recommendation for Award	₹						155			A			20 TO 10 TO	10 Me	
Start Contract Start	CV5012	Evaluate Bids & Prep. Recommendation for Award	AE		0.00								E E E E E E E E E E E E E E E E E E E			1	27 A 63
CP   CP	CV5014	Complete Recommendation for Award	ප									**************************************		10 10 mm		202	A 16 .
Start/Contract Work (25%) Complete	CV5020	Award Construction Contracts/Issue NTP	පි														
Start/Contract Work (25%) Complete	Constr	uction			2 m												
Preconstruction Meeting Begin Preconstruction Meeting Begin Preconstruction Meeting Begin Preconstruction Submittals CON Freque & Submit Shop Drawings Complete Construction Submittals CON Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (15%) Complete CON	CV6000	Project Construction Start/Issue NTP	<b>S</b>											**************************************		100 to	10 mm
Preconstruction Meeting  Begin Preconstruction Submittals  Longest Lead Procurement Item Ordered  CON  Complete Construction Submittals  Contract Work (30%+) Complete  Contract Work (30%+) Complete  Contract Work (75%) Complete  Contract Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6001	Contract Start/Contract Work (25%) Complete	CON													6	
Begin Preconstruction Submittals  Longest Lead Procurement Item Ordered  Lad Time for Longest Lead Procurement Item Ordered  Con Prepare & Submit Shop Drawings  Complete Construction Submittals  Contract Work (50%+) Complete  Contract Work (50%+) Complete  Contract Work (50%+) Complete  Contract Work (50%) Complete  Contract Work (75%) Complete  Contract Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6002	Preconstruction Meeting	CM	1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		4 A P	** ** ** ** ** ** ** ** ** ** ** **						M. Burn	FN 0	A SE SE		or to the
Longest Lead Procurement Item Ordered CON  Lead Time for Longest Lead Procurement Item CON Prepare & Submit Shop Drawings  Complete Construction Submittals  Complete Construction Submittals  Complete Construction Submittals  Contract Work (50%+) Complete  Contract Work (50%+) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6003	Begin Preconstruction Submittals	CON								TATION NO. 1	- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1-	TO BE SENTEN		n contra		
Lead Time for Longest Lead Procurement Item CON Prepare & Submit Shop Drawings Complete Construction Submittals Configuration Submit Shop Drawings Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work for confract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6004	Longest Lead Procurement Item Ordered	CON								- 1000 0						
Prepare & Submit Shop Drawings  Complete Construction Submittals  Roughing Work Start  Roughing Work Start  Perform Roughing Work  Contract Work (50%+) Complete  Contract Work (50%+) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6005	Lead Time for Longest Lead Procurement Item	CON														
Complete Construction Submittals  Roughing Work Start  Contract Work (50%+) Complete  Contract Work (50%+) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  CON  Contract Work for contract phase durations.  © Primavera Systems, Inc.  Bureau of Design & Construction Services	CV6006	Prepare & Submit Shop Drawings	NO OO		(C)	PROFILE				Market	1 04 DE				1001 1001 1001 1001 1001 1001 1001	200 00	179 KJ
Roughing Work Start     CON       Perform Roughing Work     CON       Contract Work (30%+) Complete     CON       Contract Work (75%) Complete     CON       Contract Work (75%) Complete     CON       It to section "IV Project Schedule" of the e of Work for contract phase durations.     Bureau of Design & Construction Services       © Primavera Systems, Inc.     Bureau of Design & Construction Services	CV6007	Complete Construction Submittals	NOS			3 0078	5 % % - 4-1 % - 5-0 % - 5-0 %		* 1 m 1 m		0 0 0 0 0 0 0 0						i de la constantina della cons
Perform Roughing Work  Contract Work (30%+) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  CON  DBCA-TEST  Bureau of Design & Construction Services  © Primavera Systems, Inc.	CV6011	Roughing Work Start	N S		20 100 100 100 100 100 100 100 100 100 1									A PERSONAL PROPERTY OF THE PERSONAL PROPERTY O	2 0 100 0000000 2 (40 440 2 000 0		
Contract Work (50%+) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  Contract Work (75%) Complete  CON  Contract Work (75%) Complete  CON  Bureau of Design & Construction Services  PBUFFAULTION  PBCA-TEST  Bureau of Design & Construction Services	CV6012	Perform Roughing Work	NO NO						274-96-27-4-4-						2 50 2 500 4 500 2 100 1 100 100 1 100 100	THE ST. ST.	N N
Contract Work (75%) Complete  CONTRACT  DBCA - TEST  Bureau of Design & Construction Services  © Primavera Systems, Inc.	CV6010	Contract Work (50%+) Complete	CON								- 10-						
Contract Work (75%) Complete  r to section "IV Project Schedule" of the e of Work for contract phase durations.  © Primavera Systems, Inc.	CV6013	Longest Lead Procurement Item Delivered	CON														0 10 015 H3 VI 100 000
r to section "IV Project Schedule" of the e of Work for contract phase durations.  © Primavera Systems, Inc.	CV6020	Contract Work (75%) Complete	CON			40 A					to enter the second of the sec						\$ 145 6 1861 Ad
r to section "IV Project Schedule" of the e of Work for contract phase durations.  © Primavera Systems, Inc.	NOTE		DBCA - TEST						Sheet 2 of								
© Primavera Systems, Inc.	Ref	er to section "IV Project Schedule" of the pe of Work for contract phase durations.		ureau of Desig	in & Co	nstructi	on Ser	vices			X		2		-		
		© Primavera Systems, Inc.								4	7				4	4	

Description   New Compact   Description   New Compact   Description   New Compact   Description   New Compact   Description	Activity													VIV											25 23	
Invaging was two compace	U 00/0	Description Description	Rspn	THE PERSON NAMED IN		Transian .	THE REAL PROPERTY.		THE PERSON NAMED IN	THE REAL PROPERTY.	CHIEFE CHIEFE	THE REAL PROPERTY.	THE REAL PROPERTY.					MINISTER	OTHER DE		THE REAL PROPERTY.					
Interior Finishes Start	CV0014	Roughing Work Complete	CON					N 4 60		7 0 2 0 3 0			20								4 40 24 40 20 20 20 20					
Install Interior Finishes	CV6021	Interior Finishes Start	CON							S. H. Ger		100 100 100 Tankananan 100 100 100	6 8 06 6 06 06 6 06 06 6 06 06	maranan			er er er	100 000 to		A 1	** ** **	**************************************	20 WE 2 G G2 G G G G	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10 10 10 10 10 10 10 10 10 10 10 10 10 1	
Substantial Completion   CON	CV6022	Install Interior Finishes	CON				Section and the second						and the second			=					1				1	
Substantial Completion Declared   CM   Complete Deferred Panel List/Seasonal Activities   COM   Complete Deferred Panel List/Seasonal Activities   COM   Complete Deferred Panel List/Seasonal Activities   COM   Complete Construction Complete Com	CV6030	Contract Work to Substantial Completion	CON								** ** ** ** ***** * ******			eteration or or a E %	or on mi		er ander			y y-				a or o	to the second	
Compilete Deferred Puriol. List/Seasonal Activities   CON   Project Construction Compilete   CM   Close Out Construction Compilete   CM   Close Out A/B Contracts Compilete   CM   Construction Compilete   CM   Construction Contracts Compilete   CM   Construction Contracts Compilete   CM   Project Compilete   CM   Project Compilete   CM   CM   Project Compilete   CM   CM   CM   CM   CM   CM   CM   C	CV6031	Substantial Completion Declared	CM	0 0 0 0 0 0 0 0 0 0 0 0		- W -	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10 May 10						entennos 22 R 33 to 35 to		4.8	e E ad Marie se Lee se			* ** *** * ** * *** * ** **				0 N N		
Project Construction Complete	CV6075	Complete Deferred Punch List/Seasonal Activities	CON	9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9			1 1 40 1 2 40 1 3 49 1 3 49									** *** *** ** *** ***							5 5 5 0 5 5 5 0 5 5 5 0		100 mg	
Close Out Construction Contracts   CM   CM   CM   CM   CM   CM   CM   C	CV6079	Project Construction Complete	CM							ANTENE O	20 40 5 12 70 7 2 7 7		1000 1 1000 100 1					e manta e del della							N N N	
Construction Contracts Complete	CV6080	Close Out Construction Contracts	₹					1.							#			#		1					1	
Cook Out AE Confined   CM   CM   CM   CM   CM   CM   CM   C	CV6089	Construction Contracts Complete	5	100000 100000 100000							and the second						00 00 00 00 00 00 0 0 0							B 8 :		
Project Completion Declared CM   DECA. TEST   DECA. TEST   DECA. TEST   Get to section "IV Project Schedule" of the ope of Work for contract phase durations.	CV6090	Close Out A/E Contract	Č			100 II I	POSICION P. S. S. CORRESTO STATES OF		en en e	an more	74. 00 s	100 mm 1	The second	in all a	10. 100 ·		5 (50000) (100000) (100000)				2 10	er order total		1 10 1 100 1 100		
r to section "IV Project Schedule" of the e of Work for contract phase durations.  Bureau of Design & Construction Services		Project Completion Declared	₹			******											**************************************				** ** ***					
r to section "IV Project Schedule" of the e of Work for contract phase durations.					*											4										
	NOTE: Refe	: er to section "IV Project Schedule" of the ne of Work for contract nhace durations	DBCA - TE		reau	l Jo	lesig <sub>1</sub>	3 u	Cons	truct	ion S	) Servi	ices	Sheet	30f3			5						_	-	
© Primavera Systems, Inc.		© Primavera Systems, Inc.														7	3					-		Y		



# **Building Name Building Name** UV Blower Building at Sewer Plant Locust Trade School (Academic) Quince Laurel Superintendent House MSU-A Resource Center MSU-B Pine Magnolia Red Oak Food Service New Spruce Central Warehouse Yucca Engineering (Maintenance) Power House Elm Garage for Laurel Azalea Fiscal Services Cedar Mrytle (Old Admin) Grass Multi-Purpose (Community Center) Holly Knoll Manor (Long Term) HVAC Shop & Chiller Plant Apartment (East) Apartment (West) Maple Teaberry Vine Walnut Administration Building Hospital Birch Dogwood Fern

# **EXHIBIT 'C'**

**MSU** 

Juniper

## NEW LISBON DEVELOPMENTAL CENTER NEW LISBON, NEW JERSEY 08064

#### Maintenance Department

TO: All contractors and their employees who are engaged in work on the property of New Lisbon Developmental Center

A. Follow the Developmental Center's Rules and Regulations that pertain to contractors and their employees working at the facility.

The Administration is charged with the responsibility of custody welfare of our individuals. All non-State employees are responsible and should comply with the following rules for their own protection as well as the safety of our individuals:

- No workman is to fraternize with our individuals. Any difficulties with our individuals and/or "State" employees should be handled through your supervisor or foreman. They will contact the facility Engineer in Charge.
- 2. Do not give anything to or take anything from the individuals at the facility.
- 3. Lock all cars and trucks and demobilize all equipment when unattended.
- 4. Issuance of keys to contractors and their employees, carries with it the responsibility for exercising the utmost care in their security.
- 5. No photographs are to be taken without permission of the Engineer In Charge.
- All tools and equipment must be secured before leaving at the end
  of the day. Should equipment such ladders and scaffolding be
  required to remain up overnight, the contractor shall obtain prior
  approval of the Engineer In Charge.
- 7. Warning lights must be displayed at all dangerous areas at night.
- 8. No firearms, ammunition, hunting knives or other articles of this nature are permitted on the grounds.
- No alcoholic beverages or controlled dangerous substances (CDS) are permitted on the grounds. Smoking and tobacco products are not permitted on state property. Adhere to Executive Policy #13 which is attached.

# **EXHIBIT 'D'**

- 10. Institutional Fire Regulations shall be strictly adhered to; contact the Engineer In Charge when in doubt.
- 11. Please obey 15 M.P.H. speed limit and "No Parking" areas painted yellow.
- 12. Personal items and supplies shall be stored or kept in central area designated for your use.
- 13. All excavation will be protected as directed by Engineer In Charge and those across roads must be covered with plates.
- 14. It is the responsibility of the contractor to secure all tools and equipment.
- 15. All contractors must report to Engineer In Charge's office when arriving on grounds (Monday thru Friday) and Saturday, Sunday and Holidays (PRS Office Administration Building) only when approved.
- 16. No littering permitted. Help keep our Developmental Center clean.
- 17. No materials, supplies, equipment shipped to the site for contractors will be accepted by our facility. It is the sole responsibility of the contractor to have someone on grounds to accept any item shipped.
- 18. Use of our telephone is strictly prohibited. Contractor must supply their own telephone hookup at no cost to the State of New Jersey or use cellular phones.
- 19. Fire Alarm System or Sprinkler System is not to be tampered with or shut down in any way until the Maintenance Department is notified in advance and given the ok.
- 20. There is to be no "Hot Work" welding, pipe soldering, etc. unless Maintenance is notified so permit can be filled out.

The Administration will regretfully take action against anyone violating these regulations, possibly by prohibiting them working on our property.

Revised: 3/2014, 2/17/2016 Contractorrules.doc

# EXHIBIT 'D'

New Lisbon Developmental Center	Policy Number: Executive Policy #13
Policy: Smoking Provisions	Implementation Date: <b>April 28, 2016</b>

The following policy has been established within the framework of the Center's mission and in conformance with applicable statutes, regulations, Department and Division policies.

#### I. POLICY:

The main responsibility of the New Lisbon Developmental Center (NLDC) is to protect the rights, safety and welfare of the individuals it serves. The following is designed to promote the rights of individuals, employees, and visitors to smoke at NLDC and to provide protections to individuals with PICA behaviors and the rights of non-smokers.

#### II. <u>PURPOSE</u>:

This policy provides instructions for individuals, employees and visitors who choose to smoke on the grounds of NLDC.

#### III. STANDARDS:

- A. No smoking shall be permitted inside any NLDC buildings.
- B. Smoking shall only occur in designated areas on campus that have with smoking receptacles (see attached campus map).
  - 1. Smoking areas for Individuals:
    - a. Will be established for individuals who smoke outside their home cottages and will only be used by individuals.
    - b. Individuals may smoke at the smoking areas designated for employees and visitors.
    - c. Cottage smoking areas will be located a minimum of 20 feet from cottage entrances.
    - d. Smoking receptacles shall be checked daily and cleaned and emptied as necessary by the cottage housekeeping employees.
  - 2. Smoking areas for Employees and Visitors:
    - a. Employees and visitors may only smoke in designated employee and visitor smoking areas or in their personal vehicles.
    - b. Employees and visitor smoking areas will be established at points near Birch and Maple Cottages.
    - c. Employees and visitors will not be permitted to smoke at the smoking areas for individuals located near residential cottages.
    - d. Smoking receptacles shall be checked daily and cleaned and emptied as necessary by the central housekeeping employees.

EP#13 04/2016 Page 1 of 3

New Lisbon Developmental Center	Policy Number: Executive Policy #13
Policy: Smoking Provisions	Implementation Date: April 28, 2016

- C. Employees are only permitted to smoke during their authorized 15 minute or meal breaks.
- D. Smoking materials, lighters, and matches, when not in use, must be kept out-of-sight and secured. Smoking materials are not to be left in any unsecured location (i.e. a lounge, unlocked desk or office) at any time.
- E. All NLDC Managers, Supervisors, and the Safety Officer are responsible to monitor policy compliance with employees, individuals, and visitors.
- F. All NLDC employees are responsible to report any smoking policy violations to the appropriate supervisor for follow-up.
- G. All employees, individuals, and visitors are required to adhere to the Center's smoking policy.

#### IV. ATTACHMENTS:

A. Employee Designated Smoking Locations Map

#### V. <u>REFERENCES:</u>

Public Law 1985 c. 381 (NJSA 36:3D-46 et. Seq.)
Administrative Order 4:24, "Smoking Policy for Department of Human Services Buildings"
Indoor Air Quality Standard (NJAC 12:00 1:00-13)

#### VI. Administrative Approval:

David Thomas, Chief Executive Officer

The Specially Constituted Committee-Human Rights Committee reviewed this policy on: May 2, 2016.

Policy Issued	November 20, 1989
Revision Dates	July 1, 2015; April 28, 2008; January 20, 2005; February 26, 2004; March
	30, 2001; March 27, 1998; April 30, 1995; April 15, 1994

EP#13 04/2016 Page 2 of 3

Page 3 of 3